

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
										HRRR(14) ROADWAY	HSIP(5) ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										300		300		CY	EARTH BORROW	203.30				
										1		1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
										8		8		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25				
										8		8		HR	POWER BROOM RENTAL, TYPE I	608.30				
										8		8		HR	TRUCK RENTAL	608.37				
										8		8		HR	LOADER RENTAL, TYPE I	608.40				
										669.5		669.5		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
										9		9		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
										41.5		41.5		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
										24		24		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
										275		275		HR	FLAGGERS	630.15				
										0.5	0.5	1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
											1	1		LS	TRAFFIC CONTROL (HES HSIP(5))	641.10				
										1		1		LS	TRAFFIC CONTROL (STP HRRR(14))	641.10				
										1700		1700		LF	4 INCH YELLOW LINE	646.21				
										96		96		LF	24 INCH STOP BAR	646.26				
										55		55		EACH	LETTER OR SYMBOL	646.30				
										30		30		LB	SEED	651.15				
										30		30		LB	FERTILIZER	651.18				
										0.6		0.6		TON	AGRICULTURAL LIMESTONE	651.20				
										1.5		1.5		TON	HAY MULCH	651.25				
										15		15		CY	TOPSOIL	651.35				
										300		300		SY	TEMPORARY EROSION MATTING	653.20				
										1150.32	59.91	1210.23		SF	TRAFFIC SIGNS, TYPE A	675.20				
										3015	195	3210		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
										138	3	141		EACH	REMOVING SIGNS	675.50				
										42	8	50		EACH	DELINEATOR WITH STEEL POST	676.10				
										5		5		EACH	REMOVE AND REPLACE REFLECTOR UNIT	676.15				

**PROJECT NAME:** STATEWIDE SOUTHEAST REGION  
**PROJECT NUMBER:** STP HRRR(14) / HES HSIP(5)  
**FILE NAME:** I2k022wrk.dgn  
**PROJECT LEADER:** JLS  
**DESIGNED BY:** NLA  
**COMPOSITE QUANTITY SHEET**

**PLOT DATE:** 26-JUL-2012  
**DRAWN BY:** TDS  
**CHECKED BY:** NLA  
**SHEET 3 OF 65**