STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

ATHENS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.721, RT.	A	W1-4L	30	30			6.25					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 40' SOUTH OF POLE # 543 / 4.	X		
SB	MM 0.837, LT.	E	W1-6R	48	24			8.00								2.00		30								INSTALL NEW SIGN AND POST. LOCATE IT 90' SOUTH OF POLE # 551.	X		
SB	MM 0.839, LT.	F	W1-6L	48	24			8.00								2.00		30								INSTALL NEW SIGN AND POST. LOCATE IT 85' SOUTH OF POLE # 551.	X		
SB	MM 0.893, LT.	F	W1-4L	30	30			6.25					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 16' NORTH AND ACROSS FROM POLE # 522 / VTEL / 16.	X		
NB	MM 1.040, RT.	A	W1-4R	30	30			6.25					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 50' NORTH OF POLE # 3 / 556.	X		
NB	MM ~~1.060~~, RT. TO 1.049 MM ~~1.140~~, RT. 17	AB		6	8		(14) TYPE II - 6" x 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (14) BACK-TO-BACK 60' APART ON 7 POSTS, INSTALL FIRST POST ~~160'~~ NORTH OF POLE # 3 / 556. 95'		5	
SB	MM 1.060, LT. TO MM 1.090, LT.	EF		6	8		INSTALL 5-GUARDRAIL DELINEATORS																			INSTALL (5) NEW GUARDRAIL DELINEATORS ALONG THIS SECTION OF GUARDRAIL			
SB	MM 1.090, LT. TO MM 1.140, LT.	EF					(6) TYPE II - 6" x 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (6) BACK-TO-BACK 60' APART ON 3 POSTS, INSTALL FIRST POST 160' NORTH AND ACROSS FROM POLE # 3 / 556.		5	
SB	MM 1.140, LT.	EF	D3-1	30	12			2.50								1.00		15								INSTALL NEW SIGN AND POST. LOCATE IT 32' NORTH AND ACROSS FROM POLE # 3 / 557X / VTEL / 23.		12	
		H	R1-1	30	30			6.25					X													INSTALL NEW SIGN BELOW THE D3-1 SIGN LOCATED 32' NORTH AND ACROSS FROM POLE # 3 / 557X / VTEL / 23.	X		
SB	MM 1.155, LT.	F	W5-1	36	36			9.00								2.00		30								INSTALL NEW SIGN AND POSTS. LOCATE IT 85' SOUTH AND ACROSS FROM POLE # VTEL / 23A.	X		
										EA 3 ~~3~~ 4	EA	EA	EA	EA 3	EA		FT 150	FT	FT			LB	LB	LB	LB					
								SF 52.50	SF	EA 3				EA 3		EA 10	FT 150			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: I2k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
ATHENS TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 17 OF 65