STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 5

ATHENS

| DIRECTION | MILEMARKER, STATION, OR SIGN NUMBER | LOCATION | MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE | SIGN DIMENSIONS WIDTH | SIGN DIMENSIONS HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXISTING POST RETAIN | EXISTING POST REMOVE | NO. OF NEW POSTS | SQUARE STEEL (In) 1.75 lb/ft 1.88 | SQUARE STEEL (In) 2.00 lb/ft 2.42 | SQUARE STEEL (In) 2.50 lb/ft 3.35 | TUBULAR STEEL O/(In) FOUNDATION | TUBULAR STEEL O/(In) 3.00 lb/ft 7.60 | TUBULAR STEEL O/(In) 3.50 lb/ft 9.00 | TUBULAR STEEL O/(In) 4.00 lb/ft 10.80 | TUBULAR STEEL O/(In) 5.00 lb/ft 14.60 | SIGN FRAME REQUIRED | REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK | SIGN DETAIL: DETAIL IN SHSM | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: STANDARD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| NB | 1,330 MM ~~1.321~~, RT. | A | W1-6L | 48 | 24 | | | 8.00 | | | | | | | | 2.00 | | 30 | | | | | | | | 840' INSTALL NEW SIGN AND POSTS. LOCATE IT ~~790'~~ NORTH OF POLE # VTEL / 23A . | X | | |
| NB | MM 1.345, RT. | B | W1-6R | 48 | 24 | | | 8.00 | | | | | X | | X | 2.00 | | 30 | | | | | | | | REPLACE EXISTING SIGN AND POSTS. LOCATE IT 920' NORTH OF POLE # VTEL / 23A. | X | | |
| | | B | R2-1 | 24 | 30 | | | | | | | | X | | | | | | | | | | | | | REMOVE EXISTING SIGN BELOW THE W1-6 SIGN LOCATED 920' NORTH OF POLE # VTEL / 23A. | | | |
| | | B | OM1-1 | 18 | 18 | | | | | | | | X | | | | | | | | | | | | | REMOVE EXISTING SIGN BELOW THE R2-1 SIGN LOCATED 920' NORTH OF POLE # VTEL / 23A. | | | |
| SB | MM 1.389, LT. | F | W1-2 | 30 | 30 | | | 6.25 | | | | | | | | 1.00 | | 15.75 | | | | | | | | INSTALL NEW SIGN AND POST. LOCATE IT 1150' NORTH AND ACROSS FROM POLE # VTEL / 23A. | X | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | EA | EA | EA | EA | EA | EA | | FT | FT | FT | | LB | LB | LB | LB | | | | |
| | | | | | | | | | | | | | 3 | | 1 | | | 75 | | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | | | | EA | | EA | FT | | | EA | LB | | | | | | | |
| | | | | | | | | 22.25 | | 3 | | | | 1 | | 5 | 75 | | | | | | | | | | | |

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: 12k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
ATHENS TRAFFIC SIGN SUMMARY SHEET 5

PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 19 OF 65