STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

BETHEL

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 3.650, RT.	B	D1-1	30	24		ROCHESTER ↑ ← LYMPUS						X		X											REMOVE EXISTING D1-1 SIGN AND POST LOCATED 265' EAST OF POLE # 57 / NET / 64.			
EB	MM 3.660, RT.	AB	D3-1	48	12		Brink Hill Rd	4.00								2.00		30								INSTALL NEW D3-1 SIGN ON 2 POSTS ADJACENT TO R1-1 SIGN LOCATED 320' EAST OF POLE # 57 / NET / 64.		13	
		D	R1-1	30	30		STOP	6.25					X		X	1.00		15								INSTALL NEW R1-1 SIGN AND POST. LOCATE IT 320' EAST OF POLE # 57 / NET / 64.	X		
WB	MM 3.690, LT.	F	D1-1a	72	12		↑ Rochester 6	6.00								2.00		30								INSTALL NEW SIGN AND POST. LOCATE ACROSS FROM POLE # 54 / 55 / NET / 61.		13	
		F	D1-1a	72	12		← Lympus 1	6.00																		INSTALL NEW SIGN BELOW D1-1a LOCATED ACROSS FROM POLE # 54 / 55 / NET / 61.		13	
WB	3.815 MM ~~3.780~~, LT.	F	W1-4L	30	30			6.25								1.00		15								185' EAST OF AND INSTALL NEW SIGN AND POST. LOCATE ACROSS FROM POLE # 53 / NET / 59.	X		
EB	MM 3.820, RT.	A	S3-1	36	36			9.00					MISSING ~~X~~		~~X~~	2.00		30								REPLACE EXISTING SIGN AND POST LOCATED 210' EAST OF POLE # 53 / NET / 59.	X		
EB	MM 3.930, RT.	A	W1-4R	30	30								X		X											REMOVE EXISTING SIGN AND POST LOCATED 50' EAST OF POLE # 54 / 50 / NET / 56.			
		A	W13-1	18	18		30 M.P.H.						X													REMOVE EXISTING SIGN BELOW THE W1-4 SIGN LOCATED 106' EAST OF POLE # 54 / 50 / NET / 56.			
EB	MM 3.950, RT.	A	W1-4R	30	30			6.25								1.00		15								INSTALL NEW SIGN AND POST. LOCATE IT ~~50'~~ 106' EAST OF POLE # 54 / 50 / NET / 56	X		
										EA	EA	EA	EA ~~5~~ 4	EA	EA 4		FT	FT 135	FT		LB	LB	LB	LB					
								SF 43.75	SF	EA 5				EA 4		EA 9	FT 135			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: 12k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BETHEL TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 23 OF 65