STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

BETHEL

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
		A	W13-1	18	18		30 M.P.H.	2.25																			INSTALL NEW SIGN BELOW THE W1-4 SIGN LOCATED 106' EAST OF POLE # 54 / 50 / NET / 56.	X		
WB	MM 3.955, LT. TO MM 4.050, LT.	EF		6	8		(10) TYPE II - 6" x 8" WHITE DELINEATORS																				INSTALL NEW DELINEATORS (10) BACK-TO-BACK 55' APART ON 5 POSTS, INSTALL FIRST POST 25' ~~WEST~~ EAST OF POLE # 7P55 / 49.		5	
EB	MM 4.050, RT. TO MM 4.141, RT.	AB		6	8		(14) TYPE II - 6" x 8" WHITE DELINEATORS																				INSTALL NEW DELINEATORS (14) BACK-TO-BACK 55' APART ON 7 POSTS, INSTALL FIRST POST 25' EAST OF POLE # 47 / NET / 53.		5	
WB	MM 4.141, LT.	F	W1-4R	30	30			6.25					X		X	1.00		15								REPLACE EXISTING SIGN AND POST. LOCATED 480' WEST AND ACROSS FROM POLE # 47 / NET / 53.	X		
		F	W13-1	18	18		30 M.P.H.	2.25					X													REPLACE EXISTING SIGN BELOW THE W1-4 SIGN LOCATED 480' AND ACROSS FROM POLE # 47 / NET / 53.	X		
EB	MM 4.420, RT.	A	W1-2L	30	30			6.25					X		X	1.00		15								REPLACE EXISTING SIGN AND POST. LOCATED 1955' WEST OF POLE # 47 / NET / 53.	X		
		A	W13-1	18	18		35 M.P.H.	2.25					X													REPLACE EXISTING SIGN BELOW THE W1-4 SIGN LOCATED 1955' WEST OF POLE # 47 / NET / 53.	X		
WB	MM 4.540, LT.	F	W1-2R	30	30			6.25					X		X	1.00		15								REPLACE EXISTING SIGN AND POST. LOCATED 1640' EAST AND ACROSS FROM POLE # 31-1 / 26-1.	X		
		F	W13-1	18	18		35 M.P.H.	2.25					X													REPLACE EXISTING SIGN BELOW THE W1-4 SIGN LOCATED 1640' EAST AND ACROSS FROM POLE # 31-1 / 26-1.	X		
EB	MM 4.680, RT.	A	W1-2L	30	30								X		X											REMOVE EXISTING SIGN AND POST. LOCATED 900' EAST OF POLE # 31-1 / 26-1.			
		A	W13-1	18	18		35 M.P.H.						X													REMOVE EXISTING SIGN BELOW THE W1-2 SIGN LOCATED 900' EAST OF POLE # 31-1 / 26-1.			
										EA 8	EA	EA	EA	EA 4	EA		FT 45	FT	FT										
								SF 27.75	SF	EA 8				EA 4		EA 3	FT 45			EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: I2k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
BETHEL TRAFFIC SIGN SUMMARY SHEET 4

PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 24 OF 65