STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

BETHEL

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							SUBTOTAL TSS SHEET 1	31.25					7		4	5		75											
							SUBTOTAL TSS SHEET 2	32.25					5		3	5		75											
							SUBTOTAL TSS SHEET 3	39.75					5		4	9		135											
							SUBTOTAL TSS SHEET 4	27.75					8		4	3		45											
							SUBTOTAL TSS SHEET 5	37.50					4		2	5		75											
							SUBTOTAL TSS SHEET 6	46.25					5		5	9		135											
							SUBTOTAL TSS SHEET 7	47.00					5		4	11		165											
							SUBTOTAL TSS SHEET 8	45.88					3		3	7		105											
							SUBTOTAL TSS SHEET 9	23.25					2		3	6		90											
							SUBTOTAL TSS SHEET 10	17.25							1	7		105											
								EA	EA	EA	EA	EA	EA		FT	FT	FT		LB	LB	LB	LB					
											44		32				945											
								SF	SF	EA				EA		EA	FT			EA	LB							
								348.13		44				32		63	945											

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: 12k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA