STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

GRAFTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
EB	MM 0.000, RT.	A	D1-1a	54	8		SAXTONS RIVER ↑ 7						X		X											REMOVE EXISTING SIGN ASSEMBLY AND POST LOCATED ON THE SOUTHWEST END OF BRIDGE.			
		A	D1-1a	54	8		CAMBRIDGEPORT ↑ ~~7~~ 4						X		X														
		A	M3-3	24	12		SOUTH						X																
		A	M1-5	24	24		35						X																
		A	M6-3	21	15		↑ 0125 1306 0379						X X								MM WAS TAKEN TO THE TOWN GARAGE								
		A	M3-2	24	12		EAST						X																
		A	M1-5	24	24		121						X																
		A	M6-3	21	15		↑																						
EB	MM 0.000, RT.	A	D1-1a	72	12		← Chester 7	6.00								2.00		30								INSTALL A NEW ASSEMBLY AND POSTS. LOCATE IT ON THE SOUTHWEST END OF BRIDGE. (LOCATION IS 780' WEST AND ACROSS FROM POLE # 3/31/VTC/17). USE A TYPE B SIGN FRAME. ROUTE MARKERS - BLACK TEXT & BORDER ON A WHITE BACKGROUND		14	
		A	D1-1a	72	12		↑ Cambridgeport 4	6.00																				14	
		A	D1-1a	72	12		↑ Saxtons River 7	6.00																				14	
		A	M3-1	24	12		NORTH	2.00																					E-136C
		A	M1-5	24	24		35	4.00																			X		
		A	M6-1	21	15		←	2.19																			X		
		A	M3-3	24	12		SOUTH	2.00																			X		
								SF 28.19	SF	EA 7	EA	EA	EA ~~7~~ 8	EA 2	EA	EA 2	FT	FT 30	FT	EA	LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: I2k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
GRAFTON TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 32 OF 65