STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

GRAFTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
		C	D1-1a	54	8		← SAXTONS RIVER 7						X		X											REMOVE EXISTING ASSEMBLY LOCATED ON THE SOUTHEAST CORNER OF THE BRIDGE AREA. (660' WEST AND ACROSS FROM POLE # 3 / 31 / VTC / 17).			
		C	M3-3	24	12		SOUTH						X																
		C	M1-5	24	24		35						X																
		C	M6-1L	21	15		←						X																
		C	M3-2	24	12		EAST						X																
		C	M1-5	24	24		121						X																
		C	M6-1L	21	15		←						X																
EB	MM 0.200 RT.	C	D1-1a	72	12		← Cambridgeport 4	6.00								2.00		30										14	
		C	D1-1a	72	12		← Saxtons River 7	6.00																				14	
		C	D1-1a	72	12		N. Windham 10 →	6.00																				14	
		C	M3-1	24	12		~~NORTH~~ SOUTH	2.00																	3C	INSTALL NEW ASSEMBLY LOCATED ON THE SOUTHEAST CORNER OF THE BRIDGE AREA. (660' WEST AND ACROSS FROM POLE # 3 / 31 / VTC / 17). INSTALL ROUTE MARKERS ON A 3TYPEC SIGN FRAME. ROUTE MARKERS TO BE BLACK TEXT & BORDER ON A WHITE BACKGROUND	X		
		C	M1-5	24	24		35	4.00																					E-136C
		C	M6-1L	21	15		←	2.19																			X		
		C	M3-3	24	12		SOUTH	2.00																			X		
		C	M1-5	30	24		121	5.00																					E-136C
										EA 7	EA	EA		EA 1			FT 30				LB	LB	LB	LB				
								SF 33.19	SF	EA 7				EA 1		EA 2	FT 30			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: 12k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
GRAFTON TRAFFIC SIGN SUMMARY SHEET 4

PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 35 OF 65