STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 6

GRAFTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
		F	W1-2R	30	30								X		X												REMOVE EXISTING SIGN AND POST LOCATED 285' EAST AND ACROSS FROM POLE # 30 / VTC / 18.			
WB	MM 0.258, LT.	F	VW-054	30	30			6.25					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 470' EAST AND ACROSS FROM POLE # 30 / VTC / 18.		14	
WB	MM 0.364, LT.	F	R2-1	24	30			~~5.00~~					X		X	~~1.00~~		~~15~~		REMOVAL ONLY. SIGN WAS ONLY 121' FROM NEW SIGN AT WB MM 0.387 LT BELOW						~~REPLACE EXISTING SIGN AND POST LOCATED 80' WEST AND ACROSS FROM POLE # 34 / 75 / VTEL / 23.~~	X		
WB	MM 0.380, LT.	F	W1-2R	30	30								X		X												REMOVE EXISTING SIGN AND POST LOCATED ACROSS FROM POLE # 34 / 75 / VTEL / 23.			
EB	MM 0.387, LT.	A	R2-1	24	30			5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 45' EAST OF POLE # 34 / 75 / VTEL / 23.	X		
WB	MM 0.387, LT.	F	R2-1	24	30			5.00								1.00		15								INSTALL NEW SIGN AND POST LOCATED 45' EAST AND ACROSS FROM POLE # 34 / 75 / VTEL / 23.	X		
WB	MM 0.428, LT.	F	W3-5	36	36			9.00								2.00		30								REPLACE THE EXISTING RSA SIGN WITH A NEW W3-5 SIGN AND POSTS LOCATED 260' EAST AND ACROSS FROM POLE # 34 / 75 / VTEL / 23.	X		
		F	R2-5A	24	30								X		X												REMOVE THE EXISTING SIGN AND POST LOCATED 260' EAST AND ACROSS FROM POLE # 34 / 75 / VTEL / 23.			
								SF ~~30.25~~ 25.25	SF	EA 6	EA	EA	EA 6	EA 6	EA	EA 6	FT 90	FT	FT	EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: I2k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
GRAFTON TRAFFIC SIGN SUMMARY SHEET 6

PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 37 OF 65