STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 9

GRAFTON

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB WB	MM 1.368, LT. MM 1.841 SEE BELOW	F	VW-542	36	36		WATCH FOR SNOW FROM ROOF	9.00 ~~6.25~~								2.00		30								INSTALL NEW SIGN AND POST LOCATED 130' EAST OF POLE # ~~3 / 2.~~ 1-42		12	
EB	MM 1.953, RT.	A	TOWN SIGN	30	30		HIDDEN DRIVES						X		X											REMOVE SIGN AND POST.			
		A	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25								1.00		15								REPLACE EXISTING HIDDEN DRIVES WITH A NEW VW-054 SIGN AND POST. LOCATE IT 53' WEST OF POLE # VTEL / F2 / 5.		14	
WB	MM 2.153, LT.	E	TOWN SIGN	15	24		VT 121 VT 35						X		X											REMOVE EXISTING SIGN AND POST LOCATED 15' EAST OF POLE # VTEL / 59.			
		F	W1-2L	30	30			6.25					X X SIGN WAS UNREADABLE			1.00		15								REPLACE EXISTING SIGN AND POST LOCATED 15' EAST OF POLE # VTEL / 59.	X		
EB	MM 2.234, RT.	A	W8-13	36	36		BRIDGE ICES BEFORE ROAD	9.00								2.00		30								REPLACE EXISTING SIGN AND POST LOCATED 440' EAST AND ACROSS FROM POLE # VTEL / 59.	X		
		A	VW-005	30	30		BRIDGES FREEZE BEFORE ROAD						X		X											REMOVE SIGN AND POST.			
WB	MM 2.348, LT.	F	W8-13	36	36		BRIDGE ICES BEFORE ROAD	9.00								2.00		30								REPLACE EXISTING SIGN AND POST LOCATED 85' WEST OF POLE # 3 / 401 / VTEL / 64-1.	X		
WB	MM 1.841	F	R2-1	24	30		SPEED LIMIT 40			X				X						SIGN WAS NOT ON PROJECT PLANS									
										EA	EA	EA	EA ~~4~~ 5	EA	EA 3		FT	FT 120	FT		LB	LB	LB	LB					
								SF ~~36.75~~ 39.50	SF	EA 4				EA 3		EA 8	FT 120			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: 12k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
GRAFTON TRAFFIC SIGN SUMMARY SHEET 9
PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 40 OF 65