STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

RANDOLPH

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 1.380, RT.	A	W1-2R	30	30			6.25								1.00		15								INSTALL NEW ASSEMBLY 50' EAST AND ACROSS FROM POLE # 78/41/26.	X		
		A	W13-1	18	18			2.25																		INSTALL BELOW W1-2 R SIGN ON SAME POST.	X		
WB	MM 1.410, LT. TO MM 1.455, LT.	E F		6	8		(8) TYPE II - 6" x 8" WHITE DELINEATORS																			INSTALL NEW WHITE DELINEATORS (8) BACK TO BACK 70' APART ON 4 POSTS, PUT FIRST POST 232' EAST OF POLE # 78/41/26.		5	
WB	MM 1.490, LT.	F	W1-2L	30	30			6.25								1.00		15								INSTALL NEW ASSEMBLY 30' WEST OF POLE # 8-1/43-1.	X		
		F	W13-1	18	18			2.25																		INSTALL BELOW W1-2 L SIGN ON SAME POST.	X		
EB	MM 2.040, RT.	A	R2-1	24	30								X		X											REMOVE EXISTING SIGN AND POST.	X		
		A	R2-1	24	30			5.00								1.00		15								INSTALL NEW ASSEMBLY 111' WEST OF POLE # ~~V239.~~ VZ39	X		
WB	MM 2.040, LT.	F	R2-1	24	30								X		X											REMOVE EXISTING SIGN AND POST.	X		
		F	R2-1	24	30			5.00								1.00		15								INSTALL NEW ASSEMBLY 111' WEST AND ACROSS FROM POLE # V239.	X		
										EA	EA	EA	EA 2	EA	EA 2		FT	FT 60	FT		LB	LB	LB	LB					
								SF 27.00	SF	EA 2				EA 2		EA 4	FT 60			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: 12k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
RANDOLPH TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA