STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

SPRINGFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							FRENCH MEADOW ROAD																						
SB	MM 0.025, LT.	G	W1-7	48	24			8.00								2.00		30									INSTALL A NEW W1-7 SIGN AND POSTS. LOCATE IT ACROSS FROM BELLOWS RD INTERSECTION.	X		
NB	MM 0.028, RT.	AB	D3-1	42	12			3.50					X														INSTALL NEW SIGN ABOVE STOP SIGN ON SAME POST LOCATED 42' NORTH AND ACROSS FROM POLE # 7.		12	
	MM 0.028, RT.	D	R1-1	30	30			6.25					X		X	1.00		15									REPLACE EXISTING SIGN AND POST LOCATED 42' NORTH AND ACROSS FROM POLE # 7.	X		
NB	MM ~~0.037~~ 0.000, RT.	A	W8-3	36	36		THIS SIGN WAS MOVED DOWN STATION 200' AS TOWN REQUESTED.	9.00								2.00		30									INSTALL A NEW W8-3 SIGN AND POSTS. LOCATE IT 143' SOUTH OF POLE # 8 / CTC / 6 / 2.	X		
NB	MM 0.083, RT.	A	R2-1	24	30			5.00					X		X	1.00		15									REPLACE EXISTING R2-1 SIGN AND POST. LOCATE IT 100' NORTH AND ACROSS FROM POLE # 8 / CTC / 6 / 2.	X		
SB	MM 0.089, LT.	F	W2-1	30	30			6.25								1.00		15									INSTALL A NEW W2-2 SIGN AND POST. LOCATE IT 60' SOUTH OF POLE # 9 / CTC / 6-3.	X		
		F	W16-8P	30	8			1.68																			INSTALL A NEW W16-8P SIGN BELOW THE W2-2 SIGN LOCATED 60' SOUTH OF POLE # 9 / CTC / 6-3.		12	
SB	MM 0.153, LT.	F	R2-1	24	30			5.00					X X		X	1.00		15									REPLACE EXISTING R2-1 SIGN AND POST. LOCATE IT 280' NORTH OF POLE # 9 / CTC / 6-3.	X		
NB	MM 0.753, RT.	A	R2-1	24	30			5.00					X X		X	1.00		15									REPLACE EXISTING R2-1 SIGN AND POST. LOCATE IT 206' SOUTH AND ACROSS FROM POLE # CVP / 49.	X		
SB	MM 0.816, LT. TO MM 0.844, LT.	E F		6	8		(6) TYPE II - 6" x 8" WHITE DELINEATORS																				INSTALL NEW DELINEATORS (6) BACK-TO-BACK 50' APART ON 3 POSTS. PUT THE FIRST POST ~~127'~~ NORTH 240' OF POLE # CVP / ~~49~~ 149		12	
										EA	EA	EA	EA ~~4~~ 7	EA	EA 4		FT	FT 135	FT									
								SF 49.68	SF	EA 4				EA 4		EA 9	FT 135			EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: I2k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SPRINGFIELD TRAFFIC SIGN SUMMARY SHEET I SHEET 49 OF 65