STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

WEATHERSFIELD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O (In) FOUNDATION	TUBULAR STEEL O (In) 3.00 lb/ft 7.60	TUBULAR STEEL O (In) 3.50 lb/ft 9.00	TUBULAR STEEL O (In) 4.00 lb/ft 10.80	TUBULAR STEEL O (In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM -0.001, LT.	F	R2-1	24	30		SPEED LIMIT 25 / NO PARKING OVERNIGHT						X X		X												REMOVE SIGN AND POST.			
SB	MM 0.000, LT.	F	R2-1	24	30		SPEED LIMIT 25	5.00								1.00		15									INSTALL NEW R2-1 SIGN AND POST ACROSS FROM THE TOWNLINE SIGN.	X		
NB	MM 0.000, RT.	C	VD-024	72	10		Weathersfield | Springfield	5.00								2.00		30									INSTALL A NEW TOWN LINE SIGN. LOCATE IT 1215' SOUTH AND ACROSS FROM POLE # CTC / 41 (AT BREAK IN PAVEMENT).		12	
NB	MM 0.003, RT.	A	R2-1	24	30		SPEED LIMIT 40	5.00								1.00		15									INSTALL A NEW R2-1 SIGN AND POST. LOCATE IT 15' NORTH OF THE TOWN LINE.	X		
NB	MM 0.110, RT.	A	R2-1	24	30		SPEED LIMIT 40						X		X												REMOVE THE EXISTING R2-1 SIGN AND POST LOCATED 645' SOUTH AND ACROSS FROM POLE # CTC / 41.			
SB	MM 0.038, LT.	~~A~~	~~W3-1~~	~~30~~	~~30~~			~~6.25~~								~~1.00~~		~~15~~								SIGN WAS NOT INSTALLED. INCORRECT LOCATION	~~INSTALL A NEW W3-1 SIGN AND POST. LOCATED 200 FT NORTH OF THE TOWNLINE~~	X		
NB	MM 0.283, RT.	A	W2-2R	36	36			9.00								2.00		30									INSTALL A NEW W2-2R SIGN AND POST. LOCATE IT 270' NORTH AND ACROSS FROM POLE # CTC / 41.	X		
		A	W16-8P	48	8		Wellwood Orchard Rd	2.68																			INSTALL A NEW W16-8P SIGN BELOW THE W2-2 R SIGN. LOCATE IT 270' NORTH AND ACROSS FROM POLE # CTC / 41.		12	
SB	MM 0.340, LT.	G	W1-7	48	24			8.00								2.00		30									INSTALL A NEW W1-7 SIGN AND POST. LOCATE IT ACROSS FROM WELLWOOD ORCHARD RD. 50' NORTH AND ACROSS FROM POLE # CTC / 43.	X		
SB	MM 0.400, LT.	F	W2-2L	36	36			9.00								2.00		30									INSTALL A NEW W2-2L SIGN AND POST. LOCATE IT 130' SOUTH OF POLE # 72 / 51 / CTC / 43-3.	X		
										EA	EA	EA	EA ~~2~~ 3	EA	EA 2			FT 165				LB	LB	LB	LB					
								SF ~~49.93~~ 43.68	SF				EA 2		EA 2	EA 11		FT 165		EA		LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STP HRRR(14)

FILE NAME: 12k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
WEATHERSFIELD TSS SHEET 1

PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 53 OF 65