STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

CHESTER

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.040, LT.	F	R2-1	24	30					X				X													RETAIN EXISTING SIGN AND POST 370 FT SOUTH FROM A PULL OFF AREA.			
NB	MM 0.089, RT	A	R2-1	24	30			5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST 112 FT SOUTH OF AND ACROSS FROM A PULL OFF AREA.	X		
NB	MM 0.500, LT.	A	VW-202	30	30					X				X													RETAIN EXISTING SIGN AND POST 620 FT SOUTH FROM A GRAVEL DRIVE.			
NB ~~SB~~	MM 0.618, RT.	A	W7-1	30	30			6.25								1.00		15								INSTALL NEW SIGN AND POLE 50 FT NORTH FROM GRAVEL DRIVE.	X		
SB	MM 0.6263, LT. TO MM 0.7210, LT.	F E		6	8		(8) TYPE II - 6" x 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (8) BACK-TO-BACK 125 FT APART ON 4 POSTS. INSTALL FIRST 96 FT NORTH AND ACROSS FROM GRAVEL DRIVE.		5	
SB	MM 0.705, LT.	F	VW-202	30	30					X				X													RETAIN EXISTING SIGN AND POST 512 FT NORTH OF AND ACROSS FROM THE GRAVEL DRIVE.			
NB	MM 0.8161, RT. TO MM 0.8919, RT.	A B		6	8		(8) TYPE II - 6" x 8" WHITE DELINEATORS																			INSTALL NEW DELINEATORS (8) BACK-TO-BACK 100 FT APART ON 4 POSTS. INSTALL FIRST 400 FT SOUTH FROM THE END OF GUARDRAIL.		5	
NB	MM 0.835, RT.	A	W2-2	30	30			6.25								2.00		30								INSTALL NEW SIGN AND POST 300 FT SOUTH FROM THE END OF GUARDRAIL.	X		
		A	W16-8P	42	8			2.33																		INSTALL NEW PLAQUE BELOW W2-2 SIGN ON THE SAME POSTS.		60	
										EA 3	EA	EA	EA 1	EA 3	EA 1		FT	FT 60	FT		LB	LB	LB	LB					
								SF 19.83	SF	EA 4				EA 4		EA 4	FT 60			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: HES HSIP(5)

FILE NAME: 12k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
CHESTER TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: JLS
SHEET 62 OF 65