STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

CHESTER

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHS = STANDARD HIGHWAY SIGN BOOK	SIGN DETAIL DETAIL IN SHS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.898, RT.	C	W1-7	48	24			8.00								2.00		30								INSTALL NEW SIGN AND POSTS RIGHT ACROSS FROM POPPLE DUNGEON RD AND GRAFTON RD INTERSECTION.	X		
SB	MM 0.949, LT.	F	W2-2	30	30			6.25								2.00		30								INSTALL NEW SIGN AND POSTS 75 FT NORTH OF POLE # 25.	X		
		F	W16-8P	42	8		Popple Dungeon Rd	2.33																		INSTALL NEW PLAQUE BELOW W2-2 SIGN ON THE SAME POSTS.		60	
							POPPLE DUNGEON RD.																						
EB	MM 0.000, LT.	A	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE EXISTING SIGN AND POST ON THE SOUTHWEST CORNER OF POPPLE DUNGEON RD AND GRAFTON RD INTERSECTION.	X		
		CD	D3-1	72	12		Popple Dungeon Rd	6.00					X		2-X	2.00		30								INSTALL NEW SIGN ON 2-POSTS ~~ADJACENT TO STOP SIGN~~ LOCATED ON ~~THE SOUTHWEST~~ THE NORTHEAST CORNER OF POPPLE DUNGEON RD AND GRAFTON RD INTERSECTION. AT REMOVAL LOCATION		60	
WB	MM 0.022, LT.	F	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1.00		15								REPLACE EXISTING SIGN AND POST 116 FT FROM THE NORTHWEST CORNER OF POPPLE DUNGEON RD AND GRAFTON RD INTERSECTION.	X		
EB	MM 0.029, LT.	A	W3-1	30	30			6.25								1.00		15								INSTALL NEW SIGN AND POST 155 FT FROM THE SOUTHWEST CORNER OF POPPLE DUNGEON RD AND GRAFTON RD INTERSECTION.	X		
										EA	EA	EA	EA ~~2~~ 3	EA	EA ~~2~~ 4		FT	FT 135	FT		LB	LB	LB	LB					
								SF 40.08	SF	EA 2				EA 2		EA 9	FT 135			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: HES HSIP(5)

FILE NAME: 12k022wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
CHESTER TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 23-JUL-2012
DRAWN BY: TDS
CHECKED BY: JLS
SHEET 63 OF 65