



NOTES

- SEE DETAILS ON SHEET 50.
- ALL TREE BRANCHES THAT EXTEND WITHIN A VERTICAL PLANE 10 FEET BEYOND THE NORTH AND SOUTH EDGE OF THE BRIDGE SHALL BE CUT BACK TO THE TRUNK. ALL BRANCHES TO BE CUT SHALL BE APPROVED BY THE RESIDENT ENGINEER PRIOR TO COMPLETING THE WORK. ALL WORK WILL BE PAID UNDER ITEM 201.30, THINNING AND TRIMMING.
- REMOVE AND SALVAGE WOOD POLE AT WEST END OF BRIDGE TO UTILITY COMPANY. PAYMENT WILL BE INCLUDED IN ITEM 502.10, SHORING SUPERSTRUCTURE.
- INSTALLATION, REMOVAL AND RESETTING REFLECTORIZED PLASTIC DRUMS AS SHOWN ON THE PLANS WILL BE PAID UNDER ITEM 641.10, TRAFFIC CONTROL.

SCALE: 1/16" = 1'-0"
0 8 16

Hoyle, Tanner & Associates, Inc.

HTA PROJECT	MODEL
904225	904225gpe

PROJECT NAME:	TOWNSHEND	FILE NAME:	904225gpe.dgn	PLOT DATE:	8/13/2015	
PROJECT NUMBER:	STP SCTT(I)	PROJECT LEADER:	M.D.SARGENT	DRAWN BY:	T.A.GELINAS	
			DESIGNED BY:	J.C.RIPLEY	CHECKED BY:	S.T.JAMES
			GENERAL PLAN & ELEVATION	SHEET 15 OF 60		

8/13/2015 1:56:42 PM c:\h\hoyle\tanner\904225gpe.dgn