

COMPOSITE QUANTITY SHEET 1

FAIRFIELD BRF 0281(25)				FAIRFIELD BRO 1448(41)				TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
1								1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (BRF 0281(25))	201.10				
				1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (BRO 1448(41))	201.10				
400				250				650		CY	COMMON EXCAVATION	203.15				
						5		5		CY	SOLID ROCK EXCAVATION	203.16				
		270				340		610		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
1				1				2		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
		50				100		150		CY	STRUCTURE EXCAVATION	204.25				
		10				60		70		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
240								240		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
450				180				630		CY	SUBBASE OF CRUSHED GRAVEL, COARSE GRADED	301.25				
10				90				100		CY	AGGREGATE SURFACE COURSE	401.10				
15								15		CY	AGGREGATE SHOULDERS, IN PLACE	402.10				
6								6		CWT	EMULSIFIED ASPHALT	404.65				
1								1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
		1						1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING (BRF 0281(25))	504.10				
						1		1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING (BRO 1448(41))	504.10				
		300				100		400		LF	STEEL PILING, HP 12 X 84	505.165				
		2						2		EACH	DYNAMIC PILE LOADING TEST	505.45				
		2400				1800		4200		LB	STRUCTURAL STEEL (FPQ)	506.60				
		220				162		382		LF	GROUTING SHEAR KEYS	510.24				
		48						48		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10				
		125						125		SY	MEMBRANE WATERPROOFING, SPRAY APPLIED	520.10				
48								48		LF	JOINT SEALER, HOT POURED	524.11				
		100				112.5		212.5		LF	BRIDGE RAILING, GALVANIZED HDSB / FASCIA MOUNTED / STEEL TUBING	525.44				
		1						1		EACH	REMOVAL OF STRUCTURE (605 SF - EST.)	529.15				
						1		1		EACH	REMOVAL OF STRUCTURE (705 SF - EST.)	529.15				
		12				16		28		EACH	BEARING DEVICE ASSEMBLY, PLAIN ELASTOMERIC PAD	531.16				
											BEGIN OPTION AA					
		1						1		LS	PRECAST CONCRETE STRUCTURE (ABUTMENT #1)(BRF 0281(25))	540.10				
		1						1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE)(ABUTMENT #1)(BRF 0281(25))	900.645				
											END OPTION AA					
											BEGIN OPTION BB					
						1		1		LS	PRECAST CONCRETE STRUCTURE (ABUTMENT #1)(BRO 1448(41))	540.10				
						1		1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE)(ABUTMENT #1)(BRO 1448(41))	900.645				
											END OPTION BB					

PROJECT NAME: FAIRFIELD	PLOT DATE: 11-SEP-2014
PROJECT NUMBER: BRF 0281(25) & BRO 1448(41)	DRAWN BY: K. FRIEDLAND
FILE NAME: sl2j156qs_composite.dgn	CHECKED BY: J. SALVATORI
PROJECT LEADER: R. YOUNG	SHEET 3 OF 69
DESIGNED BY: R. KLINEFELTER	
COMPOSITE QUANTITY SHEET 1	