

# COMPOSITE QUANTITY SHEET 2

FAIRFIELD BRF 0281(25)				FAIRFIELD BRO 1448(41)				TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
											BEGIN OPTION CC					
		1						1		LS	PRECAST CONCRETE STRUCTURE (ABUTMENT #2)(BRF 0281(25))	540.10				
		1						1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE)(ABUTMENT #2)(BRF 0281(25))	900.645				
											END OPTION CC					
											BEGIN OPTION DD					
						1		1		LS	PRECAST CONCRETE STRUCTURE (ABUTMENT #2)(BRO 1448(41))	540.10				
						1		1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE)(ABUTMENT #2)(BRO 1448(41))	900.645				
											END OPTION DD					
											BEGIN OPTION EE					
		1						1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB #1)	540.10				
		1						1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE)(APPROACH SLAB #1)	900.645				
											END OPTION EE					
											BEGIN OPTION FF					
		1						1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB #2)	540.10				
		1						1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE)(APPROACH SLAB #2)	900.645				
											END OPTION FF					
	1				1			2		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
25								25		CY	STONE FILL, TYPE I	613.10				
		170				230		400		CY	STONE FILL, TYPE III	613.12				
58				58				116		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
4				4				8		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
4				4				8		EACH	GUARDRAIL APPROACH SECTION, GALV HD STEEL BEAM	621.737				
148				93				241		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
500								500		HR	FLAGGERS	630.15				
			0.5				0.5	1		LS	FIELD OFFICE, ENGINEERS	631.10				
			0.5				0.5	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
			1				1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
			1500				1500	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
0.5				0.5				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
650								650		LF	4 INCH YELLOW LINE	646.21				
600				160				760		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
		190				280		470		SY	GEOTEXTILE UNDER STONE FILL	649.31				
	180				180			360		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
	60				80			140		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
	5				5			10		LB	SEED	651.15				
	40				30			70		LB	FERTILIZER	651.18				
	1				1			2		TON	AGRICULTURAL LIMESTONE	651.20				
	1				1			2		TON	HAY MULCH	651.25				

PROJECT NAME: FAIRFIELD  
 PROJECT NUMBER: BRF 0281(25) & BRO 1448(41)  
 FILE NAME: sl2j156qs\_composite.dgn  
 PROJECT LEADER: R. YOUNG  
 DESIGNED BY: R. KLINEFELTER  
 COMPOSITE QUANTITY SHEET 2  
 PLOT DATE: 11-SEP-2014  
 DRAWN BY: K. FRIEDLAND  
 CHECKED BY: J. SALVATORI  
 SHEET 4 OF 69