

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
														BEGIN OPTION FF					
									1		1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB #2)	540.10				
									1		1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE)(APPROACH SLAB #2)	900.645				
														END OPTION FF					
								1			1		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
							25				25		CY	STONE FILL, TYPE I	613.10				
									170		170		CY	STONE FILL, TYPE III	613.12				
							58				58		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
							4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
							4				4		EACH	GUARDRAIL APPROACH SECTION, GALV HD STEEL BEAM	621.737				
							148				148		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
							500				500		HR	FLAGGERS	630.15				
										0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10				
										0.5	0.5		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							0.5				0.5		LS	MOBILIZATION/DEMobilIZATION	635.11				
							650				650		LF	4 INCH YELLOW LINE	646.21				
							600				600		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
									190		190		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								180			180		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								60			60		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								5			5		LB	SEED	651.15				
								40			40		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								20			20		CY	TOPSOIL	651.35				
									110		110		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN (BRF 0281(25))	652.10				
								40			40		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BRF 0281(25))	652.30				
								60			60		SY	TEMPORARY EROSION MATTING	653.20				
								36			36		CY	VEHICLE TRACKING PAD	653.35				
								290			290		LF	BARRIER FENCE	653.50				
								280			280		LF	PROJECT DEMARCATION FENCE	653.55				
							0.66				0.66		SF	TRAFFIC SIGNS, TYPE A	675.20				
								16			16		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
								4			4		EACH	DELINEATOR WITH STEEL POST	676.10				
									6		6		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET)(FPQ)	900.608				
									264		264		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE SOLID SLABS)(15" x 48")	900.640				

PROJECT NAME: FAIRFIELD
 PROJECT NUMBER: BRF 0281(25)
 FILE NAME: sl2j156qs.dgn
 PROJECT LEADER: R. YOUNG
 DESIGNED BY: R. KLINEFELTER
 QUANTITY SHEET 2
 PLOT DATE: 11-SEP-2014
 DRAWN BY: K. FRIEDLAND
 CHECKED BY: J. SALVATORI
 SHEET 10 OF 69