

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								30			30		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								25			25		CY	TOPSOIL	651.35				
									70		70		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN (BRO 1448(41))	652.10				
								20			20		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BRO 1448(41))	652.30				
								18			18		CY	VEHICLE TRACKING PAD	653.35				
								480			480		LF	BARRIER FENCE	653.50				
							0.66				0.66		SF	TRAFFIC SIGNS, TYPE A	675.20				
							30				30		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							2				2		EACH	REMOVING SIGNS	675.50				
							2				2		EACH	ERECTING SALVAGED SIGNS	675.60				
							4				4		EACH	DELINEATOR WITH STEEL POST	676.10				
									4		4		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET)(FPQ)	900.608				
									50		50		LF	SPECIAL PROVISION (PRE-EXCAVATION OF INTEGRAL ABUTMENT PILES, EARTH)	900.640				
									30		30		LF	SPECIAL PROVISION (PRE-EXCAVATION OF INTEGRAL ABUTMENT PILES, ROCK)	900.640				
									216		216		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE SOLID SLABS)(21" x 48")	900.640				
							0.5				0.5		LS	SPECIAL PROVISION (CPM SCHEDULE)	900.645				
							1				1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)(BRO 1448(41))	900.645				

PROJECT NAME: FAIRFIELD
 PROJECT NUMBER: BRO 1448(41)
 FILE NAME: sl2j170qs.dgn
 PROJECT LEADER: R. YOUNG
 DESIGNED BY: R. KLINEFELTER
 QUANTITY SHEET 2
 PLOT DATE: 18-AUG-2014
 DRAWN BY: K. FRIEDLAND
 CHECKED BY: J. SALVATORI
 SHEET 42 OF 69