



- △ DENOTES FORM FINISH
- △ DENOTES FLOAT FINISH
- △ DENOTES SMOOTH TROWEL FINISH

MARK: FA-AB1	QTY.: 1	WT.: 34.54 T	VOL.: 17.06 cy
MARK: FA-AB2	QTY.: 1	WT.: 34.54 T	VOL.: 17.06 cy
MATERIAL LIST / ABUTMENT			
ITEM	MARK	DESCRIPTION	QTY./ABUT.
1		#6 x 2'-11" (LEVEL II, DUAL COATED)	24 24
2			
3			
4			
5			
6		BRIDGE PLAQUE (SUPPLIED BY OTHERS)	1
7		SET OF (4) 0.60" x 270 KSI STRAND LIFTING LOOPS	2 2
8		6" x 5'-1 3/4" (MAX.) CORRUGATED STEEL SLEEVE (GALV.)	16 16
9		2'-0" x 5'-1 1/2" CORRUGATED STEEL SLEEVE (GALV.)	4 4
10			

Vermont Agency of Transportation
RECEIVED
CK'D BY RK/JW OK'D BY RY
February 12, 2015
RESUBMIT No Approved AsNoted
BY RY DATE 02/12/2015
△ 2-10-15 REVISED PER VT AOT COMMENTS

APPROVAL STAMP:	J.P. CARRARA & SONS INC. Precast & Prestress Manufacturer 244 ONE STR. MIDDLEBURY, VERMONT 05753 Phone: (802)388-6361 Fax: (802)388-8010	A.L. ST. ONGE CONTRACTOR MONTGOMERY, VERMONT
STATE OF VERMONT AGENCY OF TRANSPORTATION COUNTY OF FRANKLIN		DATE: NOV. 10, 2014 SCALE: NOTED
TOWN OF FAIRFIELD SOUTH ROAD, FAS 0281 (RURAL MAJOR COLLECTOR) BRIDGE NO.: 14 PROJECT NO.: BRF 0281(25)		CHKD: B.C. DFTM: B.L. JOB NO: 23446-014
PRECAST ABUTMENT DIMENSIONAL DETAILS		DWG. NO: ABI