



- NOTES:
1. POSTS 17 AND 19 SHALL BE EXTRA LONG POSTS. POSTS 12, 13, 14, 14, 15, 16 AND 18 SHALL BE STANDARD LENGTH.
  2. POSTS 17 AND 19 SHALL BE FASTENED TO THE RAIL USING DETAIL "A".
  3. THE DRAWING INDICATES THE TERMINAL INSTALLED ON LEVEL GROUND. WHEN INSTALLED OVER A SLOPE OR DITCH, THE TERMINAL END SHOULD BE PUSHED DOWN WITH THE EQUIVALENT OF APPROXIMATELY 100 LBS EFFORT TO DEPRESS THE TERMINAL DOWN.
  4. POSTS 14, 16 AND 18 SHALL NOT BE CONNECTED TO BOX BEAM GUARDRAIL.
  5. SEE BOX BEAM DETAIL SHEET FOR SPLICE AND TYPICAL END ASSEMBLY DETAILS.

PROJECT NAME: CLARENDON	
PROJECT NUMBER: BRO 1443(48)	
FILE NAME: s12j160rallde+.dgn	PLOT DATE: 10-SEP-2015
PROJECT LEADER: K. HIGGINS	DRAWN BY: S. COLEY
DESIGNED BY: J. GRIGAS	CHECKED BY: G. LAROCHE
GUARDRAIL END ASSEMBLY TYPE IIA	SHEET 26 OF 59