

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL CE ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
									400		400		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								250			250		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								100			100		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								5			5		LB	SEED	651.15				
								5			5		LB	SEED, WINTER RYE	651.17				
								40			40		LB	FERTILIZER	651.18				
								1			1		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								40			40		CY	TOPSOIL	651.35				
									240		240		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								<del>40</del>			<del>40</del>		<del>HR</del>	<del>MONITORING EPSC PLAN</del>	<del>652.20</del>				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								300			300		SY	TEMPORARY EROSION MATTING	653.20				
								60			60		CY	VEHICLE TRACKING PAD	653.35				
								180			180		LF	BARRIER FENCE	653.50				
								510			510		LF	PROJECT DEMARCATION FENCE	653.55				
							0.66				0.66		SF	TRAFFIC SIGNS, TYPE A	675.20				
							16				16		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							4				4		EACH	DELINEATOR WITH STEEL POST	676.10				
									16		16		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET)(FPQ)	900.608				
									171		171		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NEXT D BEAM)(NEXT 28D)	900.640				
								1			1		LS	SPECIAL PROVISION (CPM SCHEDULE)	900.645				
								1			1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				
								1			1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)	900.650				
								1			1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
								1			1		LU	SPECIAL PROVISION (MXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
								100			100		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: CAMBRIDGE  
PROJECT NUMBER: BRO 1448(39)

FILE NAME: sl2j166qs.dgn  
PROJECT LEADER: K. HIGGINS  
DESIGNED BY: G. LAROCHE  
QUANTITY SHEET 2

PLOT DATE: 29-AUG-2014  
DRAWN BY: J. SALVATORI  
CHECKED BY: G. LAROCHE  
SHEET 6 OF 34