

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								300	330		630		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								15			15		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								120			120		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								10			10		LB	SEED	651.15				
								10			10		LB	SEED, WINTER RYE	651.17				
								50			50		LB	FERTILIZER	651.18				
								0.5			0.5		TON	AGRICULTURAL LIMESTONE	651.20				
								0.5			0.5		TON	HAY MULCH	651.25				
							65				65		CY	TOPSOIL	651.35				
									230		230		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								40			40		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								530			530		SY	TEMPORARY EROSION MATTING	653.20				
								40			40		CY	VEHICLE TRACKING PAD	653.35				
								360			360		LF	BARRIER FENCE	653.50				
								120			120		LF	PROJECT DEMARCATION FENCE	653.55				
							31				31		SF	TRAFFIC SIGNS, TYPE A	675.20				
							72				72		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							2				2		EACH	REMOVING SIGNS	675.50				
									10		10		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET)(FPQ)	900.608				
									10		10		HR	SPECIAL PROVISION (UNEXPECTED OBSTRUCTION DRILLING)	900.630				
									270		270		LF	SPECIAL PROVISION (MICROPILE, CASED)(7 INCHES)	900.640				
									220		220		LF	SPECIAL PROVISION (MICROPILE, UNCASD)(6.18 INCHES)	900.640				
									215		215		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE NEXT D BEAMS)(NEXT 32 D)	900.640				
							1				1		LS	SPECIAL PROVISION (CPM SCHEDULE)	900.645				
									1		1		LS	SPECIAL PROVISION (FURNISHING EQUIPMENT FOR INSTALLING MICROPILES)	900.645				
									1		1		LS	SPECIAL PROVISION (REMOVAL OF TEMPORARY BRIDGE)	900.645				
							1				1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(N.A.B.I.)	900.650				
							1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
							1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
							375		50		425		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				
							6				6		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683				

ITEM 900.680 SPECIAL PROVISION  
(BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)

235 TONS COLD PLANE AREAS (EST.)  
64 TONS TYPE IIS (ROADWAY)  
64 TONS TYPE IVS (ROADWAY)  
14 TONS OVER APPROACH SLABS  
33 TONS ON BRIDGE  
15 TONS ROUND

425 TONS TOTAL

PROJECT NAME: ENOSBURG  
PROJECT NUMBER: BRO 1448(40)

FILE NAME: ...\\xx Bridge Quantities.dgn PLOT DATE: 10/22/2013  
PROJECT LEADER: G. BOGUE DRAWN BY: E. ALLING  
DESIGNED BY: G. GOYETTE CHECKED BY: G. GOYETTE  
BRIDGE AND ROADWAY QUANTITY SHEET - QS 2 SHEET 7 OF 46

