

COMPOSITE QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES				
										BO 1449(33) BRIDGE 58	BHF 0286(5) BRIDGE 20	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
															BEGIN OPTION JJ					
											54	54		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215				
											54	54		LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415				
											54	54		LF	18" CPEP(SL)	601.2615				
															END OPTION JJ					
										65		65		LF	CLEANING CULV. PIPE, IN-PLACE [0 TO 24 IN., INCL.]	601.995				
											122	122		LF	CLEANING CULV. PIPE, IN-PLACE [GREATER THAN 24 IN.]	601.996				
											2	2		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18				
										25	25	50		MGAL	DUST CONTROL WITH WATER	609.10				
										19	3	22		CY	STONE FILL, TYPE I	613.10				
											70	70		CY	STONE FILL, TYPE II	613.11				
										595		595		CY	STONE FILL, TYPE III	613.12				
											1	1		EACH	WOOD MARKER POSTS	619.15				
										159	68	227		LF	REMOVAL OF EXISTING FENCE	620.55				
										163		163		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
											26	26		LF	BOX BEAM GUARDRAIL	621.30				
										2		2		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
										4		4		EACH	GUARDRAIL APPROACH SECTION, GALV HD STEEL BEAM	621.737				
										25		25		LF	REMOVE AND RESET GUARDRAIL	621.75				
										246		246		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
										40	40	80		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
										100	100	200		HR	FLAGGERS	630.15				
										0.5	0.5	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										0.5	0.5	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										0.5	0.5	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1500	1500	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
										520	520	1040		HR	EMPLOYEE TRAINEESHIP	634.10				
										0.5	0.5	1		LS	MOBILIZATION/DEMobilIZATION	635.11				
										3	2	5		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
										376	760	1136		LF	4 INCH WHITE LINE	646.20				
										299	600	899		LF	4 INCH YELLOW LINE	646.21				
										14.3		14.3		LF	24 INCH STOP BAR	646.26				
										4		4		EACH	LETTER OR SYMBOL	646.30				
										61.2		61.2		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
										1020		1020		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
										760	120	880		SY	GEOTEXTILE UNDER STONE FILL	649.31				
										220	68	288		SY	GEOTEXTILE FOR SILT FENCE	649.51				
										222	113	335		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
										17.6	5	22.6		LB	SEED	651.15				

PROJECT NAME: BARTON VILLAGE
 PROJECT NUMBER: BO 1449(33) & BHF 0286(5)
 FILE NAME: z13j078qtycomp.dgn
 PROJECT LEADER: J. OLUND
 DESIGNED BY: B. TOOTHAKER
 COMPOSITE QUANTITY SHEET 3
 PLOT DATE: 9/8/2016
 DRAWN BY: S. MORGAN
 CHECKED BY: T. POULIN
 SHEET 4 OF 110

REV	DATE	DESCRIPTION
△	9/12/2016	REMOVED ITEM

TYLININTERNATIONAL