

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
														BEGIN OPTION GG					
									1		1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB 1) (BRIDGE 58)	540.10				
									1		1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE) (APPROACH SLAB 1) (BRIDGE 58)	900.645				
														END OPTION GG					
														BEGIN OPTION HH					
									1		1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB 2) (BRIDGE 58)	540.10				
									1		1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE) (APPROACH SLAB 2) (BRIDGE 58)	900.645				
														END OPTION HH					
						13					13		LF	24" CSP .064 (2-2/3 X 1/2)	601.0025				
						65					65		LF	CLEANING CULV. PIPE, IN-PLACE [0 TO 24 IN., INCL.]	601.995				
						25					25		MGAL	DUST CONTROL WITH WATER	609.10				
						19					19		CY	STONE FILL, TYPE I	613.10				
									595		595		CY	STONE FILL, TYPE III	613.12				
						159					159		LF	REMOVAL OF EXISTING FENCE	620.55				
						163					163		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
						2					2		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
						4					4		EACH	GUARDRAIL APPROACH SECTION, GALV HD STEEL BEAM	621.737				
						25					25		LF	REMOVE AND RESET GUARDRAIL	621.75				
						246					246		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						40					40		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						100					100		HR	FLAGGERS	630.15				
										0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10				
										0.5	0.5		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							520				520		HR	EMPLOYEE TRAINEESHIP	634.10				
						0.5					0.5		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						3					3		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
						376					376		LF	4 INCH WHITE LINE	646.20				
						299					299		LF	4 INCH YELLOW LINE	646.21				
						14.3					14.3		LF	24 INCH STOP BAR	646.26				
						4					4		EACH	LETTER OR SYMBOL	646.30				
						61.2					61.2		SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85				
						1020					1020		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
									760		760		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								220			220		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								222			222		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								17.6			17.6		LB	SEED	651.15				
								5			5		LB	SEED, WINTER RYE	651.17				

PROJECT NAME: BARTON VILLAGE
 PROJECT NUMBER: BO 1449(33)
 FILE NAME: z13j078qty.dgn
 PROJECT LEADER: J. OLUND
 DESIGNED BY: B. TOOTHAKER
 QUANTITY SHEET 2
 PLOT DATE: 7/26/2016
 DRAWN BY: S. MORGAN
 CHECKED BY: T. POULIN
 SHEET 12 OF 110

