



NOTES:

1. SHRUB PLANTINGS ARE TO BE 24"-30" CORNUS SERICEA (RED STEMMED DOGWOOD) IN A THREE GALLON CONTAINER AND WILL BE PAID UNDER ITEM 656.35, "DECIDUOUS SHRUBS."
 - PLANTING BED 1 SHALL BE 20 FT BY 5 FT AND 2 FT DEEP AND CONTAIN 2 ROWS OF 6 SHRUBS EACH.
 - PLANTING BED 2 SHALL BE 12 FT BY 5 FT AND 2 FT DEEP AND CONTAIN 2 ROWS OF 3 SHRUBS EACH.
2. SHRUBS ARE TO BE PLANTED 3 FT ON CENTER IN ALTERNATING ROWS.
3. FINAL SHRUB AND PLANTING BED LOCATIONS TO BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.
4. FOR DETAILS ON INSTALLATION SEE EPSC DETAIL SHEET 2.
5. BACKFILL FOR PLANTING BEDS WILL BE PAID UNDER ITEM 656.80, "LANDSCAPE BACKFILL, TRUCK MEASUREMENT."
6. WATERING AND MAINTENANCE SHALL BE PERFORMED IN ACCORDANCE WITH SECTION 656 OF THE STANDARD SPECIFICATIONS.

EPSC - FINAL SITE PLAN

SCALE 1" = 20'-0"
 20 0 20

TYLIN INTERNATIONAL	PROJECT NAME: BARTON VILLAGE	PLOT DATE: 7/26/2016
	PROJECT NUMBER: BO 1449(33)	DRAWN BY: B. TOOTHAKER
	FILE NAME: z13j078ero.dgn	CHECKED BY: J. OLUND
	DESIGNED BY: B. TOOTHAKER	SHEET 50 OF 110
	EPSC FINAL SITE PLAN	