

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
ROADWAY	ROADWAY (NO FEDERAL/STATE)	TRAINING	EROSION CONTROL	WELL, PUMP, ETC. (NO FEDERAL/STATE)	BRIDGE	BRIDGE (NO FEDERAL/STATE)	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS		
											BEGIN OPTION DD							
					1			1		LS	PRECAST CONCRETE STRUCTURE (APPROACH SLAB 2) (BRIDGE 20)	540.10						
					1			1		LS	SPECIAL PROVISION (CONTRACTOR-FABRICATED PRECAST CONCRETE STRUCTURE) (APPROACH SLAB 2) (BRIDGE 20)	900.645						
											END OPTION DD							
											BEGIN OPTION II							
35								35		LF	12" CAAP .060 (2-2/3 X 1/2)	601.0205						
35								35		LF	12" PCCSP .064 (2-2/3 X 1/2)	601.0405						
35								35		LF	12" CPEP(SL)	601.2605						
											END OPTION II							
											BEGIN OPTION JJ							
54								54		LF	18" CAAP .060 (2-2/3 X 1/2)	601.0215						
54								54		LF	18" PCCSP .064 (2-2/3 X 1/2)	601.0415						
54								54		LF	18" CPEP(SL)	601.2615						
											END OPTION JJ							
122								122		LF	CLEANING CULV. PIPE, IN-PLACE [GREATER THAN 24 IN.]	601.996						
2								2		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18						
25								25		MGAL	DUST CONTROL WITH WATER	609.10						
					3			3		CY	STONE FILL, TYPE I	613.10						
					70			70		CY	STONE FILL, TYPE II	613.11						
1								1		EACH	WOOD MARKER POSTS	619.15						
68								68		LF	REMOVAL OF EXISTING FENCE	620.55						
26								26		LF	BOX BEAM GUARDRAIL	621.30						
40								40		HR	UNIFORMED TRAFFIC OFFICERS	630.10						
100								100		HR	FLAGGERS	630.15						
							0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10						
							0.5	0.5		LS	TESTING EQUIPMENT, CONCRETE	631.16						
							0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17						
							1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26						
		520						520		HR	EMPLOYEE TRAINEESHIP	634.10						
0.5								0.5		LS	MOBILIZATION/DEMOBILIZATION	635.11						
2								2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15						
760								760		LF	4 INCH WHITE LINE	646.20						
600								600		LF	4 INCH YELLOW LINE	646.21						
					120			120		SY	GEOTEXTILE UNDER STONE FILL	649.31						
				68				68		SY	GEOTEXTILE FOR SILT FENCE	649.51						
				113				113		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61						
				5				5		LB	SEED	651.15						
				5				5		LB	SEED, WINTER RYE	651.17						
				39				39		LB	FERTILIZER	651.18						

PROJECT NAME: BARTON VILLAGE  
 PROJECT NUMBER: BHF 0286(5)  
 FILE NAME: z12j172q+ty.dgn  
 PROJECT LEADER: J. OLUND  
 DESIGNED BY: B. TOOTHAKER  
 QUANTITY SHEET 2  
 PLOT DATE: 9/8/2016  
 DRAWN BY: S. MORGAN  
 CHECKED BY: T. POULIN  
 SHEET 60 OF 110

**TYLIN**INTERNATIONAL

REV	DATE	DESCRIPTION
△	9/12/2016	REMOVED ITEM