

# QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
		ROADWAY	ROADWAY (NO FEDERAL/STATE)	TRAINING	EROSION CONTROL	WELL, PUMP, ETC. (NO FEDERAL/STATE)	BRIDGE	BRIDGE (NO FEDERAL/STATE)	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					0.2					0.2		TON	AGRICULTURAL LIMESTONE	651.20				
					0.2					0.2		TON	HAY MULCH	651.25				
		41								41		CY	TOPSOIL	651.35				
					1					1		LS	EPSC PLAN (BRIDGE 20)	652.10				
					10					10		HR	MONITORING EPSC PLAN	652.20				
					1					1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BRIDGE 20)	652.30				
					30					30		CY	VEHICLE TRACKING PAD	653.35				
					5					5		EACH	INLET PROTECTION DEVICE, TYPE I	653.40				
					374					374		LF	PROJECT DEMARCATION FENCE	653.55				
		0.6								0.6		SF	TRAFFIC SIGNS, TYPE A	675.20				
		12								12		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
		2								2		EACH	REMOVING SIGNS	675.50				
							10			10		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, RAPID SET) (FPQ)	900.608				
			226					96		322		CY	SPECIAL PROVISION (MANAGEMENT OF PETROLEUM CONTAMINATED SOILS)	900.608				
							43000			43000		DL	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE) (N.A.B.I.) (BRIDGE 20)	900.615				
							8			8		EACH	SPECIAL PROVISION (CPM SCHEDULE)	900.620				
		4								4		EACH	SPECIAL PROVISION (GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAIL)	900.620				
						5				5		EACH	SPECIAL PROVISION (MONITORING WELL)	900.620				
							32			32		LF	SPECIAL PROVISION (PRE-EXCAVATION OF INTEGRAL ABUTMENT PILES, ROCK)	900.640				
							360			360		LF	SPECIAL PROVISION (PRESTRESSED CONCRETE SOLID SLABS)(15" X 48")	900.640				
							1			1		LS	SPECIAL PROVISION (CONSTRUCTION VIBRATION AND CRACK MONITORING)	900.645				
		1								1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) (BRIDGE 20)	900.645				
		1								1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, TYPE IVB) (N.A.B.I.)	900.650				
		96					52			148		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, TYPE IVB)	900.680				

PROJECT NAME: BARTON VILLAGE  
 PROJECT NUMBER: BHF 0286(5)  
 FILE NAME: z12j172qty.dgn  
 PROJECT LEADER: J. OLUND  
 DESIGNED BY: B. TOOTHAKER  
 QUANTITY SHEET 3  
 PLOT DATE: 7/26/2016  
 DRAWN BY: S. MORGAN  
 CHECKED BY: T. POULIN  
 SHEET 61 OF 110

