

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES

TOTALS

DESCRIPTIONS

DETAILED SUMMARY OF QUANTITIES

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	FULL C. E. ITEMS	BRIDGE	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
							1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
										150	150		CY	STRUCTURE EXCAVATION	204.25				
										39	39		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
							54				54		CY	AGGREGATE SURFACE COURSE	401.10				
										8	8		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34				
										350	350		LB	REINFORCING STEEL, LEVEL I	507.11				
										1	1		GAL	WATER REPELLENT, SILANE	514.10				
										3.9	3.9		MFBM	STRUCTURAL LUMBER AND TIMBER, UNTREATED	522.20				
										3.5	3.5		MFBM	NONSTRUCTURAL LUMBER, UNTREATED	522.30				
										1	1		EACH	PARTIAL REMOVAL OF STRUCTURE	529.20				
										65	65		CY	DRY MASONRY	602.20				
										15	15		CY	REBUILT STONE MASONRY	602.35				
										33	33		SY	REPAIRING STONE MASONRY	602.40				
										15	15		CY	STONE FILL, TYPE II	613.11				
							24				24		LF	PLANK RAIL	621.15				
							31				31		LF	STEEL BACKED TIMBER GUARDRAIL	621.18				
							2				2		EACH	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81				
									1		1		LS	FIELD OFFICE, ENGINEERS	631.10				
									3000		3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							1				1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
							1				1		LS	TRAFFIC CONTROL	641.10				
										30	30		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								20			20		SY	GEOTEXTILE FOR SILT FENCE	649.51				
								10			10		LB	SEED	651.15				
								10			10		LB	FERTILIZER	651.18				
								0.2			0.2		TON	AGRICULTURAL LIMESTONE	651.20				
								1			1		TON	HAY MULCH	651.25				
								4			4		CY	TOPSOIL	651.35				
								10			10		SY	TEMPORARY EROSION MATTING	653.20				
								10			10		CY	VEHICLE TRACKING PAD	653.35				
								150			150		LF	PROJECT DEMARCATION FENCE	653.55				
							35				35		SF	TRAFFIC SIGNS, TYPE A	675.20				
							110				110		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
										12	12		EACH	SPECIAL PROVISION (Slate Roof Repairs)	900.620				
										16	16		EACH	SPECIAL PROVISION (Wood Epoxy Repairs)	900.620				
							43				43		LF	SPECIAL PROVISION (Steel Backed Timber Guardrail - Fascia Mounted)	900.640				
										1	1		LS	SPECIAL PROVISION (Rehabilitating Covered Bridge Superstructure)	900.645				
										1	1		LS	SPECIAL PROVISION (Timber Coating, Environmental Protection)	900.645				
										1	1		LS	SPECIAL PROVISION (Timber Coating, Fire Retardant)	900.645				

PROJECT NAME: **Shrewsbury**
 PROJECT NUMBER: **BHO 1443(49)**
 FILE NAME: 12j350Q.xls PLOT DATE: 12/04/2014
 PROJECT LEADER: Mark Sargent DRAWN BY: Curt Weeber
 DESIGNED BY: John Weaver CHECKED BY: John Weaver
 QUANTITY SHEET #1 SHEET 4 OF 23