

QUANTITY SHEET 1

| SUMMARY OF ESTIMATED QUANTITIES | | | | | | | | | | | TOTALS | | DESCRIPTIONS | | | | DETAILED SUMMARY OF QUANTITIES | | |
|---------------------------------|--|--|--|--|--|--|--|--|-------------------------|------------------------|-------------|-------|--------------|--|-------------|-------|--------------------------------|------|-------|
| | | | | | | | | | STP HRRR(12) ROADWAY | HES HSIP(3) ROADWAY | GRAND TOTAL | FINAL | UNIT | ITEMS | ITEM NUMBER | ROUND | QUANTITIES | UNIT | ITEMS |
| | | | | | | | | | 150 | | 150 | | CY | EARTH BORROW | 203.30 | EST. | | | |
| | | | | | | | | | 1 | | 1 | | CY | TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.) | 204.22 | - | | | |
| | | | | | | | | | 8 | | 8 | | HR | ALL PURPOSE EXCAVATOR RENTAL, TYPE I | 608.25 | EST. | | | |
| | | | | | | | | | 8 | | 8 | | HR | POWER BROOM RENTAL, TYPE I | 608.30 | EST. | | | |
| | | | | | | | | | 8 | | 8 | | HR | TRUCK RENTAL | 608.37 | EST. | | | |
| | | | | | | | | | 8 | | 8 | | HR | LOADER RENTAL, TYPE I | 608.40 | EST. | | | |
| | | | | | | | | | 113 | | 113 | | LF | STEEL BEAM GUARDRAIL, GALVANIZED | 621.20 | - | | | |
| | | | | | | | | | 6 | | 6 | | EACH | ANCHOR FOR STEEL BEAM RAIL | 621.60 | - | | | |
| | | | | | | | | | 113 | | 113 | | LF | REMOVAL AND DISPOSAL OF GUARDRAIL | 621.80 | - | | | |
| | | | | | | | | | 24 | | 24 | | HR | UNIFORMED TRAFFIC OFFICERS | 630.10 | EST. | | | |
| | | | | | | | | | 275 | | 275 | | HR | FLAGGERS | 630.15 | EST. | | | |
| | | | | | | | | | 0.5 | 0.5 | 1 | | LS | MOBILIZATION/DEMOBILIZATION | 635.11 | - | | | |
| | | | | | | | | | | 1 | 1 | | LS | TRAFFIC CONTROL (HES HSIP(3)) | 641.10 | - | | | |
| | | | | | | | | | 1 | | 1 | | LS | TRAFFIC CONTROL (STP HRRR(12)) | 641.10 | - | | | |
| | | | | | | | | | 1050 | | 1050 | | LF | 4 INCH WHITE LINE | 646.20 | 15.1 | | | |
| | | | | | | | | | 1600 | | 1600 | | LF | 4 INCH YELLOW LINE | 646.21 | 22.4 | | | |
| | | | | | | | | | 208 | | 208 | | LF | 24 INCH STOP BAR | 646.26 | EST. | | | |
| | | | | | | | | | 45 | | 45 | | EACH | LETTER OR SYMBOL | 646.30 | - | | | |
| | | | | | | | | | 15 | | 15 | | LB | SEED | 651.15 | EST. | | | |
| | | | | | | | | | 15 | | 15 | | LB | FERTILIZER | 651.18 | EST. | | | |
| | | | | | | | | | 0.3 | | 0.3 | | TON | AGRICULTURAL LIMESTONE | 651.20 | EST. | | | |
| | | | | | | | | | 0.75 | | 0.75 | | TON | HAY MULCH | 651.25 | EST. | | | |
| | | | | | | | | | 7.5 | | 7.5 | | CY | TOPSOIL | 651.35 | EST. | | | |
| | | | | | | | | | 150 | | 150 | | SY | TEMPORARY EROSION MATTING | 653.20 | EST. | | | |
| | | | | | | | | | 977.42 | 59 | 1036.42 | | SF | TRAFFIC SIGNS, TYPE A | 675.20 | - | | | |
| | | | | | | | | | 2535 | 150 | 2685 | | LF | SQUARE TUBE SIGN POST AND ANCHOR | 675.341 | EST. | | | |
| | | | | | | | | | 126 | 5 | 131 | | EACH | REMOVING SIGNS | 675.50 | EST. | | | |
| | | | | | | | | | 55 | | 55 | | EACH | DELINEATOR WITH STEEL POST | 676.10 | EST. | | | |