

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES													TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
												ROADWAY	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
													150	150	CY	EARTH BORROW	203.30	EST.			
													1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			
													8	8	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
													8	8	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.			
													8	8	HR	TRUCK RENTAL	608.37	EST.			
													8	8	HR	LOADER RENTAL, TYPE I	608.40	EST.			
													113	113	LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
													6	6	EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
													113	113	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	-			
													24	24	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
													275	275	HR	FLAGGERS	630.15	EST.			
													0.5	0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
													1	1	LS	TRAFFIC CONTROL (STP HRRR(12))	641.10	-			
													1050	1050	LF	4 INCH WHITE LINE	646.20	15.1			
													1600	1600	LF	4 INCH YELLOW LINE	646.21	22.4			
													208	208	LF	24 INCH STOP BAR	646.26	EST.			
													45	45	EACH	LETTER OR SYMBOL	646.30	-			
													15	15	LB	SEED	651.15	EST.			
													15	15	LB	FERTILIZER	651.18	EST.			
													0.3	0.3	TON	AGRICULTURAL LIMESTONE	651.20	EST.			
													0.75	0.75	TON	HAY MULCH	651.25	EST.			
													7.5	7.5	CY	TOPSOIL	651.35	EST.			
													150	150	SY	TEMPORARY EROSION MATTING	653.20	EST.			
													977.42	977.42	SF	TRAFFIC SIGNS, TYPE A	675.20	-			
													2535	2535	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	EST.			
													126	126	EACH	REMOVING SIGNS	675.50	EST.			
													55	55	EACH	DELINEATOR WITH STEEL POST	676.10	EST.			

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(12)
FILE NAME: I2K018wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
QUANTITY SHEET

PLOT DATE: 11-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 10 **OF** 52