STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

BARRE TOWN
E COBBLE HILL RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
WB	MM 1.369, LT.	F	VW-054	30	30		HIDDEN DRIVE RIGHT						X		X											REMOVE EXISTING VW-054 SIGN AND POST LOCATED 70' EAST AND ACROSS FROM POLE # GMP / 20			
EB	MM 1.396, RT.	A	W2-2L	30	30			6.25								1.00		15								INSTALL NEW W2-2 SIGN AND POST. LOCATE 100' EAST AND ACROSS FROM POLE # GMP / 19. TOWN TO CUT TREE BRANCHES AROUND SIGN FOR BETTER VISIBILITY.	X		
		A	W16-8P	30	8		Sunnyside Dr	1.675																		INSTALL NEW W16-8P SIGN BELOW THE W2-2 SIGN LOCATED 100' EAST AND ACROSS FROM POLE # GMP / 19		11	
WB	MM 1.468, LT.	EF	D3-1	60	12		Sunnyside Dr	5.00					X		X	2.00		30								REPLACE EXISTING D3-1 SIGN INSTALL ON 2 POSTS ADJACENT TO THE R1-1 SIGN LOCATED 290' EAST OF POLE # GMP / 19. INSTALL ON 2 POSTS ADJACENT TO STOP SIGN.		11	
		H	R1-1	30	30		STOP	6.25								1.00		15								INSTALL NEW R1-1 SIGN AND POST. LOCATE 290' EAST OF POLE # GMP / 19	X		
WB	MM 1.472 LT. + 50 FT.	G	R2-1	24	30		SPEED LIMIT 25	5.00								1.00		15								REPLACE EXISTING R2-1 SIGN AT THE SUNNYSIDE DR. INTERSECTION	X		
WB	MM 1.509, LT.	F	W2-2R	30	30			6.25								1.00		15								INSTALL NEW W2-2 SIGN AND POST. LOCATE 130' WEST OF POLE # GMP / 16 AND OR 10' EAST OF DRIVEWAY	X		
		F	W16-8P	30	8		Sunnyside Dr	1.675																		INSTALL NEW W16-8P SIGN BELOW THE W2-2 SIGN LOCATED 130' WEST OF POLE # GMP / 16 AND OR 10' EAST OF DRIVEWAY		11	
WB	MM 1.533, LT.	F	W2-2R	30	30								X		X											REMOVE EXISTING W2-2 SIGN AND POST LOCATED 10' WEST OF POLE # GMP / 16			
		F	TOWN SIGN	30	30		HIDDEN DRIVE						X													REMOVE EXISTING TOWN SIGN BELOW THE W2-2 SIGN LOCATED 10' WEST OF POLE # GMP / 16			
										EA 4	EA	EA	EA	EA	EA 3			FT 90									
								SF 32.10	SF	EA 4				EA 3		EA 6		FT 90		EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(12)

FILE NAME: 12k018wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 11-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
BARRE TOWN TRAFFIC SIGN SUMMARY SHEET3 SHEET 15 OF 52