STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

LYNDON
S WHEELOCK RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
SB	MM 0.008, LT.	F	R1-1	30	30		STOP / MEMORIAL DRIVE / S. WHEELOCK ROAD	6.25				2	X		~~X~~ 3	1.00		15								REPLACE EXISTING R1-1 SIGN AND POST LOCATED 40' NORTH OF INTERSECTION SALVAGE 2 STREET SIGNS	X		
NB	MM 0.014, RT.	A	TOWN SIGN	24	30		SPEED ZONE AHEAD						X													REMOVE EXISTING R2-5a SIGN LOCATED 75' NORTH OF INTERSECTION			
		A	R2-1	24	30		SPEED LIMIT 35	5.00							X	1.00		15								INSTALL NEW R2-1 SIGN AND POST LOCATED 75' NORTH OF INTERSECTION	X		
		A	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00					X														REPLACE EXISTING VR-017 SIGN LOCATED 75' NORTH OF INTERSECTION ABOVE R2-1 SIGN ON THE SAME POST		5	
NB	MM 0.033, RT.	A	R2-1	24	30		SPEED LIMIT 35						X		X											REMOVE EXISTING R2-1 SIGN AND POST LOCATED 175' NORTH OF INTERSECTION			
NB	MM 0.105, RT.	A	W1-10R	36	36			9.00							X	2.00		30								INSTALL NEW W1-10 R SIGN AND POSTS. LOCATE IT 255' SOUTH AND ACROSS FROM POLE # 6.4A	X		
		A	W16-8P	36	8		Cross St	2.00																		INSTALL NEW W16-8P SIGN BELOW THE W1-10 SIGN LOCATED 255' SOUTH AND ACROSS FROM POLE # 6.4A		11	
NB	MM 0.127, RT.	A	TOWN SIGN	30	30		HIDDEN DRIVE AHEAD	6.25					X		X											REMOVE EXISTING SIGN AND POST LOCATED 140 FT. SOUTH AND ACROSS FROM POLE # 6.4A			
NB	MM 0.127, RT.	A	VW-060	30	30		~~HIDDEN DRIVES~~ HIDDEN DRIVE	6.25					X		X	1.00		15								REPLACE EXISTING SIGN WITH A NEW VW-060 SIGN AND POST LOCATED 140' SOUTH AND ACROSS FROM POLE # 6.4A		11	
SB	MM 0.201, LT.	H	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE EXISTING R1-1 SIGN AND POST LOCATED 140' SOUTH AND ACROSS FROM POLE # 6-3-1 / 5-4 A	X		
										EA	EA	EA ~~2~~	EA 7	EA	EA ~~7~~ 8		FT	FT ~~90~~	FT								
								SF 46.00	SF	EA ~~7~~ 9				EA	EA ~~7~~ 8	EA 6	FT 90			EA	LB	LB	LB	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(12)

FILE NAME: 12k018wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
LYNDON TRAFFIC SIGN SUMMARY SHEET 1

PLOT DATE: 11-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 26 OF 52