STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

WILLIAMSTOWN
GRANITEVILLE RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (In) 1.75 lb/ft 1.88	SQUARE STEEL (In) 2.00 lb/ft 2.42	SQUARE STEEL (In) 2.50 lb/ft 3.35	TUBULAR STEEL O/(In) FOUNDATION	TUBULAR STEEL O/(In) 3.00 lb/ft 7.60	TUBULAR STEEL O/(In) 3.50 lb/ft 9.00	TUBULAR STEEL O/(In) 4.00 lb/ft 10.80	TUBULAR STEEL O/(In) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 0.505, RT.	A	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25								1.00		15								INSTALL A NEW VW-054 SIGN AND POST LOCATED 53' EAST OF POLE # GMP/90		12	
WB	MM 0.520, LT.	F	R2-5A	24	30		REDUCED SPEED AHEAD						X		X											REMOVE THE EXISTING R2-5A SIGN AND POST LOCATED 130' EAST AND ACROSS FROM POLE # GMP/90			
WB	MM 0.520, LT.	F	W3-5	36	36		ADVISORY SPEED LIMIT 30	9.00								2.00		30								INSTALL A NEW R2-5A SIGN AND POST LOCATED 130' EAST AND ACROSS FROM POLE # GMP/90	X		
EB	MM 0.576, RT.	A	S3-1	36	36	FYG		9.00					X		X	2.00		30								REPLACE THE EXISTING S3-1 SIGN AND POST, LOCATED 20' EAST OF POLE # GMP/86	X		
EB	MM 0.636, RT.	A	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25					X		X	1.00		15								REPLACE THE EXISTING VW-054 SIGN AND POST, LOCATED 143' EAST OF POLE # GMP/84		12	
WB	MM 0.794, LT.	F	S3-1	36	36	FYG		9.00					X		X	2.00		30								REPLACE THE EXISTING S3-1 SIGN AND POST, LOCATED 50' WEST OF POLE # GMP/79-0/NET/27 1/2	X		
EB	MM 0.889, RT.	A	W1-2R	30	30								X		X											REMOVE THE EXISTING W1-2R SIGN AND POST, LOCATED 150' EAST AND ACROSS FROM POLE # GMP/77/6/30/NET			
EB	MM 0.889, RT.	A	W1-1R	30	30			6.25								1.00		15								INSTALL A NEW W1-1R SIGN AND POST, LOCATED 150' WEST AND ACROSS FROM POLE # GMP/77/6/30/NET	X		
										EA	EA	EA	EA 5	EA	EA 5			FT 135	FT					LB	LB	LB	LB				
								SF 45.75	SF	EA 5				EA 5		EA 9		FT 135		EA	LB										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(12)

FILE NAME: 12k018wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 11-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA