STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 5

WILLIAMSTOWN
GRANITEVILLE RD

| DIRECTION | MILEMARKER, STATION, OR SIGN NUMBER | LOCATION | MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE | SIGN DIMENSIONS WIDTH | SIGN DIMENSIONS HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXISTING POST RETAIN | EXISTING POST REMOVE | NO. OF NEW POSTS | SQUARE STEEL (In) 1.75 lb/ft 1.88 | SQUARE STEEL (In) 2.00 lb/ft 2.42 | SQUARE STEEL (In) 2.50 lb/ft 3.35 | TUBULAR STEEL O/(In) FOUNDATION | TUBULAR STEEL O/(In) 3.00 lb/ft 7.60 | TUBULAR STEEL O/(In) 3.50 lb/ft 9.00 | TUBULAR STEEL O/(In) 4.00 lb/ft 10.80 | TUBULAR STEEL O/(In) 5.00 lb/ft 14.60 | SIGN FRAME REQUIRED | REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK) | SIGN DETAIL: DETAIL IN SHSM | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: STANDARD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| WB | MM 1.473, LT. + 35 FT. | G | R2-1 | 24 | 30 | | SPEED LIMIT 35 | 5.00 | | | | | X | | X | | | | | | | | | | | | REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED ON THE NORTHEASTERN CORNER OF MCGLYNN RD | X | | |
| WB | MM 1.473, LT. | G | | | | | | | | | | | | | X | | | | | | | | | | | | REMOVE EMPTY POST | | | |
| EB | MM 1.746, RT. | A | W1-2R | 30 | 30 | | | | | | | | X | | X | | | | | | | | | | | | REMOVE EXISTING W1-2 SIGN AND POST LOCATED 10' WEST OF POLE # 7 | | | |
| EB | MM 1.792, RT. | A | W1-2R | 30 | 30 | | | 6.25 | | | | | X | | X | 1.00 | | 15 | | | | | | | | | REPLACE THE EXISTING W1-2 SIGN AND POST LOCATED 10' EAST OF POLE # 8 | X | | |
| | | A | W13-1 | 18 | 18 | | 35 M.P.H. | 2.25 | | | | | | | | | | | | | | | | | | | INSTALL A NEW W13-1 SIGN BELOW THE W1-2 SIGN LOCATED 10' EAST OF POLE # 8 | X | | |
| EB | MM 1.807, RT. TO MM 1.860, RT. | AB | | 6 | 8 | | (8) TYPE II - 6" x 8" WHITE DELINEATORS | | | | | | | | | | | | | | | | | | | | INSTALL NEW DELINEATORS (8) BACK - TO - BACK 70 FEET APART ON 4 POSTS. INSTALL THE FIRST POST 70' EAST OF POLE # 8 | | 5 | |
| WB | MM 1.876, LT. | F | W1-2L | 30 | 30 | | | 6.25 | | | | | | | | 1.00 | | 15 | | | | | | | | | INSTALL A NEW W1-2 L SIGN AND POST. LOCATE IT 430' EAST AND ACROSS OF POLE # 8 | X | | |
| | | F | W13-1 | 18 | 18 | | 35 M.P.H. | 2.25 | | | | | | | | | | | | | | | | | | | INSTALL A NEW W13-1 SIGN BELOW W1-2L SIGN. LOCATE IT 430' EAST AND ACROSS OF POLE # 8 | X | | |
| WB | MM 1.880, LT. | F | W1-2L | 30 | 30 | | | | | | | | X | | X | | | | | | | | | | | | REMOVE THE EXISTING W1-2 L SIGN AND POST. LOCATED 100' WEST OF POLE # GMP/56 | | | |
| | | F | W13-1 | 18 | 18 | | 35 M.P.H. | | | | | | X | | X | | | | | | | | | | | | REMOVE THE EXISTING W13-1 SIGN BELOW W1-2L SIGN. LOCATED 100' WEST OF POLE # GMP/56 | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | EA 5 | EA | EA | EA | EA | EA 6 | | | FT 30 | | | | | | | LB | | | | |
| | | | | | | | | SF 22.00 | SF | EA 5 | | | | EA 6 | | EA 2 | | FT 30 | | EA | LB | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(12)

FILE NAME: 12k018wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
DRAWN BY: TDS
CHECKED BY: NLA
PLOT DATE: 11-JUL-2012
WILLIAMSTOWN TRAFFIC SIGN SUMMARY SHEET5
SHEET 37 OF 52