STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 7

WILLIAMSTOWN
GRANITEVILLE RD

| DIRECTION | MILEMARKER, STATION, OR SIGN NUMBER | LOCATION | MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE | SIGN DIMENSIONS WIDTH | SIGN DIMENSIONS HEIGHT | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXISTING POST RETAIN | EXISTING POST REMOVE | NO. OF NEW POSTS | SQUARE STEEL (In) 1.75 lb/ft 1.88 | SQUARE STEEL (In) 2.00 lb/ft 2.42 | SQUARE STEEL (In) 2.50 lb/ft 3.35 | FOUNDATION | TUBULAR STEEL O/(In) 3.00 lb/ft 7.60 | TUBULAR STEEL O/(In) 3.50 lb/ft 9.00 | TUBULAR STEEL O/(In) 4.00 lb/ft 10.80 | TUBULAR STEEL O/(In) 5.00 lb/ft 14.60 | SIGN FRAME REQUIRED | REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK | SIGN DETAIL: DETAIL IN SHSM | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: STANDARD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| WB | MM 2.361, LT. | E F | D3-1 | 48 | 12 | | Maclean Rd | 4.00 | | | | | | | | 2.00 | | 30 | | | | | | | | INSTALL A NEW D3-1 NEXT TO THE R1-1 SIGN LOCATED ON THE SOUTHEAST CORNER OF MACLEAN RD ON 2 POSTS | | 12 | |
| | | H | R1-1 | 30 | 30 | | STOP | 6.25 | | | | | X | | X | 1.00 | | 15 | | | | | | | | REPLACE THE EXISTING W R1-1 SIGN AND POST. LOCATE IT ON THE SOUTHEAST CORNER OF THE MACLEAN RD | X | | |
| WB | MM 2.365, LT. | E F | D3-1 | 24 | 6 | | Maclean Rd McLEAN RD | | | | | | X | | X | | | | | | | | | | | REMOVE THE EXISTING D3-1 SIGN AND POST LOCATED ON THE NORTHEAST CORNER OF THE MACLEAN RD | | | |
| WB | MM 2.365 LT. +50 FT. | G | R2-1 | 24 | 30 | | SPEED LIMIT 25 | 5.00 | | | | | X | | X | 1.00 | | 15 | | | | | | | | REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED ON THE NORTHEAST CORNER OF THE MACLEAN RD | X | | |
| WB | MM 2.393, LT. | F | W1-2L | 30 | 30 | | | 6.25 | | | | | | | | 1.00 | | 15 | | | | | | | | INSTALL A NEW W1-2 SIGN AND POST. LOCATE 140' EAST OF POLE #25K/GMP/47 | X | | |
| EB | MM 2.614, RT. | AB | D3-1 | 24 | 6 | | Adams Rd | | | | | | X | | X | | | | | | | | | | | REMOVE THE EXISTING D3-1 SIGN AND POST LOCATED ON THE SOUTHWEST CORNER OF ADAMS RD | | | |
| EB | MM 2.614, RT. + 50 FT. | C | R2-1 | 24 | 30 | | SPEED LIMIT 35 | 5.00 | | | | | X | | X | 1.00 | | 15 | | | | | | | | REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED ON THE SOUTHWEST CORNER OF ADAMS RD | X | | |
| EB | MM 2.616, RT. | CD | D3-1 | 42 | 12 | | Adams Rd | 3.50 | | | | | | | | | | | | | | | | | | INSTALL A NEW D3-1 ABOVE THE R1-1 SIGN LOCATED ON THE SOUTHEAST CORNER OF THE ADAMS RD | | 12 | |
| | | D | R1-1 | 30 | 30 | | STOP | 6.25 | | | | | X | | X | 1.00 | | 15 | | | | | | | | REPLACE THE EXISTING R1-1 SIGN AND POST. LOCATE IT ON THE SOUTHEAST CORNER OF THE ADAMS RD | X | | |
| WB | MM 2.616, LT. TO MM 2.828, LT. | EF | | 6 | 8 | | (32) TYPE II - 6" x 8" WHITE DELINEATORS | | | | | | | | | | | | | | | | | | | INSTALL NEW DELINEATORS (32) BACK - TO - BACK 70' APART ON 16 POSTS, INSTALL FIRST POST ACROSS FROM ADAMS RD | | 5 | |
| EB | MM 2.820, RT. | AB | D3-1 | 24 | 6 | | Baptist Rd | | | | | | ~~X~~ 2 | | X | | | | | | | | | | | REMOVE THE EXISTING D3-1 SIGN AND POST LOCATED ON THE SOUTHWEST CORNER OF BAPTIST ST | | | |
| EB | MM 2.820, RT. + 50 FT. | C | R2-1 | 24 | 30 | | SPEED LIMIT 35 | 5.00 | | | | | X | | X | 1.00 | | 15 | | | | | | | | REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED ON THE SOUTHWEST CORNER OF BAPTIST ST | X | | |
| | | | | | | | | | | EA | EA | EA | EA ~~8~~ 9 | EA | EA 8 | | FT | FT 120 | FT | | LB | LB | LB | LB | | | | |
| | | | | | | | | SF 41.25 | SF | EA ~~8~~ 9 | | | | EA 8 | | EA 8 | FT 120 | | | EA | LB | | | | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(12)

FILE NAME: 12k018wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
WILLIAMSTOWN TRAFFIC SIGN SUMMARY SHEET 7
PLOT DATE: 11-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 39 OF 52