STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

WILLIAMSTOWN
GRANITEVILLE RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
EB	MM 2.823, RT.	CD	D3-1	48	12		Baptist St	4.00								2.00		30								INSTALL A NEW D3-1 ON 2 POSTS ADJACENT TO THE R1-1 SIGN LOCATED ON THE SOUTHWEST CORNER OF THE BAPTIST ST.		12	
		D	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE THE EXISTING R1-1 SIGN AND POST. LOCATE IT ON THE SOUTHWEST CORNER OF THE PIRIE RD	X		
WB	MM 2.835, LT.	EF	D3-1	36	12		Pirie Rd	3.00																		INSTALL A NEW D3-1 ABOVE THE R1-1 SIGN LOCATED ON THE SOUTHEAST CORNER OF THE PIRIE RD		12	
		H	R1-1	30	30		STOP	6.25					X		X	1.00		15								REPLACE THE EXISTING R1-1 SIGN AND POST. LOCATE IT ON THE SOUTHEAST CORNER OF THE PIRIE RD	X		
WB	MM 2.838, LT.	EF	D3-1	24	6		Pirie Rd						X		X											REMOVE THE EXISTING D3-1 SIGN LOCATED ON THE NORTHEAST CORNER OF THE PIRIE RD			
WB	MM 2.838, LT. + 50 FT.	G	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1.00		15								REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED ON THE NORTHEAST CORNER OF PIRIE RD	X		
EB	MM 2.847, RT.	A	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1.00		15								REPLACE THE EXISTING R2-1 SIGN AND POST LOCATED LOCATED 50' EAST OF POLE # 75334	X		
EB	MM 2.864, RT.	A	W1-2R	30	30			6.25					X		X	1.00		15								INSTALL A NEW W2-1 SIGN AND POST LOCATED 111' WEST AND ACROSS FROM POLE # GMP/33	X		
WB	MM 2.927, LT.	F	W1-2L	30	30			6.25								1.00		15								INSTALL A NEW W2-1 SIGN AND POST LOCATED 26' WEST AND ACROSS FROM POLE # GMP/33	X		
EB	MM 2.943, RT.	A	TOWN SIGN	30	30		BLIND DRIVE						X		X											REMOVE THE EXISTING BLIND DRIVE WARNING SIGN LOCATED 58' WEST OF POLE # GMP/32			
										EA	EA	EA	EA ~~6~~ 7	EA	EA ~~6~~ 7		FT	FT 120	FT		LB	LB	LB	LB					
								SF 42.00	SF	EA ~~6~~ 7				EA ~~6~~ 7		EA 8	FT 120			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(12)

FILE NAME: 12k018wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
WILLIAMSTOWN TRAFFIC SIGN SUMMARY SHEET8

PLOT DATE: 11-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA