STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET

TOWN TOTALS

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
							BARRE TOWN TSS SUBTOTAL	193.34		1			30	1	~~25~~ 26	34		~~495~~ 510	~~15~~										
							DERBY TSS SUBTOTAL	~~186.75~~ 180.50		2			~~20~~ 24	~~2~~ 1	~~17~~ 18	~~31~~ 32		~~465~~ 480											
							LYNDON TSS SUBTOTAL	249.25				3	~~25~~ 26		~~23~~ 25	~~42~~ 40		~~630~~ 600											
							WILLIAMSTOWN TSS SUBTOTAL	348.08		1			~~51~~ 55	1	~~51~~ 53	~~62~~ 63		~~930~~ 945											
								SF ~~977.42~~ 971.17	SF	EA 4	EA	EA 3	EA ~~126~~ 135	EA ~~4~~ 3	EA ~~116~~ 122	EA 169	FT	FT ~~2520~~ 2535	FT ~~15~~	EA	LB	LB	LB	LB					
													EA ~~130~~ 142		EA ~~120~~ 125			FT 2535										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHEAST REGION
PROJECT NUMBER: STP HRRR(12)

FILE NAME: 12k018wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
TRAFFIC SIGN SUMMARY SHEET

PLOT DATE: 11-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 44 OF 52