STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

CHARLOTTE
MT PHILO RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 0.000, RT.	C	VD-024	72	10		Charlotte | Ferrisburgh	5.00								2.00		11.0 ~~30~~ 11.0									INSTALL NEW TOWN LINE SIGN. LOCATE IT 327' SOUTH OF POLE # 17		13	
NB	MM 0.040, RT.	A	W11-1	30	30			6.25								1.00		16.0 ~~15~~									INSTALL NEW W11-1 SIGN AND POST 116' SOUTH OF POLE # 17.	X		
NB	MM 0.040, RT.	A	W16-1P	18	24		SHARE THE ROAD	3.00																			INSTALL NEW PLAQUE BELOW W11-1 ON THE SAME POST.	X		
NB	MM 0.102, RT.	D	R1-1	30	30		STOP	6.25					X		X	1.00		14.0 ~~15~~									REPLACE EXISTING R1-1 SIGN AND POST LOCATED 306' SOUTH OF POLE # GMP / 6	X		
NB	MM 0.115, RT.	D	R1-1	30	30		STOP	6.25				1	X		X	1.00		14.0 ~~15~~									REPLACE EXISTING R1-1 SIGN AND POST LOCATED 26' SOUTH OF POLE # GMP / 6	X		
NB	MM 0.166, RT.	A	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1.00		13.0 ~~15~~									REPLACE EXISTING R2-1 SIGN AND POST LOCATED ADJACENT TO POLE # GMP / 8	X		
SB	MM 0.166, LT.	F	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1.00		14.0 ~~15~~									REPLACE EXISTING R2-1 SIGN AND POST LOCATED ACROSS FROM POLE # GMP / 8	X		
SB	MM 0.905, LT.	F	R2-1	24	30		SPEED LIMIT 40	5.00					X		X	1.00		14.0 ~~15~~									REPLACE EXISTING R2-1 SIGN AND POST LOCATED 270' SOUTH OF STATE PARK ROAD	X		
SB	MM 0.950, LT.	H	R1-1	30	30		STOP	6.25					X		X	1.00		14.0 ~~15~~									REPLACE EXISTING R1-1 SIGN AND POST LOCATED JUST SOUTH OF STATE PARK RD	X		
NB	MM 0.960, RT.	H	R1-1	30	30		STOP	6.25					X		X	1.00		13.0 ~~15~~									REPLACE EXISTING R1-1 SIGN AND POST LOCATED JUST NORTH AND ACROSS FROM STATE PARK RD	X		
								SF 54.25	SF	EA 1	EA	EA 7	EA 7	EA 7	EA 7	EA 10	FT	FT ~~150~~ 134	FT	EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn **PLOT DATE:** 16-JUL-2012
PROJECT LEADER: JLS **DRAWN BY:** TDS
DESIGNED BY: NLA **CHECKED BY:** NLA
CHARLOTTE ITRAFFIC SIGN SUMMARY SHEET I **SHEET** 17 **OF** 107