STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

CHARLOTTE
MT PHILO RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 2.260, LT.	F	S3-1	36	36	FYG		9.00					X		X	2.00		14.0 ~~30~~ 14.0								REPLACE EXISTING SBSA SIGN AND POSTS LOCATED ADJACENT TO POLE # 6	X		
NB	MM 2.380, RT.	A	R2-1	24	30			5.00					X		X	1.00		14.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 635' NORTH AND ACROSS FROM POLE # 6	X		
SB	MM 2.730, LT.	F	R2-1	24	30			5.00					X		X	1.00		13.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED ADJACENT TO POLE # GMP / 23 / 18	X		
SB	MM 3.090, LT.	F	TOWN SIGN	30	30								X		X											REMOVE SIGN AND POST.			
		F	VW-060	30	30			6.25								1.00		14.0 ~~15~~								INSTALL NEW SIGN AND POST LOCATED 530' SOUTH OF POLE # GMP / 33		13	
NB	MM 3.180, RT.	A	R2-1	24	30			5.00					X		X	1.00		13.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 50' SOUTH AND ACROSS FROM POLE # GMP / 33	X		
SB	MM 3.410, LT.	F	TOWN SIGN	30	30								X		X											REMOVE SIGN AND POST LOCATED 1162' NORTH OF POLE # GMP / 33			
		F	W11-1	30	30			6.25								1.00		15								INSTALL NEW SIGN AND POST.	X		
										EA	EA	EA	EA 6	EA	EA 6		FT	FT ~~105~~	FT		LB	LB	LB	LB					
								SF 36.50	SF	EA 6				EA 6		EA 7	FT ~~105~~ 97			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA