STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

CHARLOTTE
SPEAR ST

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
SB	MM 0.120, LT.	F	R2-1	24	30		SPEED LIMIT 50	5.00					~~X~~		X	1.00		14.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 50' NORTH AND ACROSS FROM POLE # GMP / 15 1/2	X		
NB	MM 0.120, RT.	A	W2-2R	30	30			6.25								1.00		NO POST ONLY BASE ~~15~~ 4								INSTALL NEW W2-2 50' NORTH OF POLE # GMP / 15 1/2	X		
		A	W16-8P	30	8		Carpenter Rd	1.67																		INSTALL NEW W16-8P BELOW THE W2-2 LOCATED 50' NORTH OF POLE # GMP / 15 1/2		13	
NB	MM 0.180, LT.	D	R1-1	30	30		STOP			X				X												RETAIN EXISTING R1-1 SIGN AND POST LOCATED AT 212' SOUTH OF POLE # GMP / 1 / 230			
NB	MM 0.220, RT.	A	R2-1	24	30		SPEED LIMIT 50	5.00								1.00		13.0 ~~15~~								INSTALL NEW R2-1 SIGN AND POST. LOCATE 15' SOUTH OF POLE # GMP / 1 / 230	X		
SB	MM 0.230, LT.	A	W2-2L	30	30			6.25								1.00		14.0 ~~15~~								INSTALL NEW W2-2 SIGN AND POST 50' NORTH AND ACROSS FROM POLE # GMP / 1 / 230	X		
		A	W16-8P	30	8		Carpenter Rd	1.67																		INSTALL NEW W16-8P BELOW THE W2-2 LOCATED 50' NORTH AND ACROSS FROM POLE # GMP / 1 / 230		13	
NB	MM 0.420, RT.	A	W1-4R	30	30			6.25								1.00		15								INSTALL NEW W1-4 R 50' NORTH OF POLE # GMP / 21	X		
NB	MM 0.700, RT.	A	W1-5L	30	30			6.25								1.00		15								INSTALL NEW W1-5 L SIGN AND POST. LOCATE 1810' SOUTH OF POLE # GMP / 10 / NET / 24-20 / 40	X		
								SF 38.34	SF	EA ~~2~~ 0				EA 2		EA 6	FT ~~90~~ 75			EA	LB							
										EA 1	EA	EA	EA 1	EA 1	EA 1		FT	FT ~~90~~	FT		LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn **PLOT DATE:** 16-JUL-2012
PROJECT LEADER: JLS **DRAWN BY:** TDS
DESIGNED BY: NLA **CHECKED BY:** NLA
CHARLOTTE 2 TRAFFIC SIGN SUMMARY SHT 1 **SHEET** 23 **OF** 107