STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

ENOSBURG
PERLEY RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.000, RT.	A	W1-10L	36	36			9.00								2.00		30								INSTALL NEW W1-10 L SIGN AND POST ADJACENT TO POLE # 18 / 139	X		
		A	W16-8P	36	8			2.00																			INSTALL NEW W16-8P BELOW THE W1-10 L SIGN LOCATED ADJACENT TO POLE # 18 / 139. INSTALL SINGLE FACED SIGN ON BOTH SIDES OF POST, RIVOT IN PLACE.		14	
NB	MM 0.053, RT.	A B	D3-1	42	12			3.50					4			1		13.0								INSTALL NEW D3-1 SIGN ABOVE NICHOLS RD STREET NAME SIGN LOCATED 120' NORTH OF POLE # 19 / 40. INSTALL SINGLE FACED SIGNS ON BOTH SIDES OF POST, RIVOT IN PLACE.		14	
NB	MM 0.053, RT.	A B	D3-1	42	12			3.50																		INSTALL NEW D3-1 SIGN ABOVE NICHOLS RD STREET NAME SIGN LOCATED 120' NORTH OF POLE # 19 / 40. INSTALL SINGLE FACED SIGNS ON BOTH SIDES OF POST, RIVOT IN PLACE.		14	
		C D	D3-1	48	12			4.00																		INSTALL NEW D3-1 SIGN OVER THE R1-2 SIGN LOCATED 120' NORTH OF POLE # 19 / 40. INSTALL SINGLE FACED SIGNS ON BOTH SIDES OF POST, RIVOT IN PLACE.		14	
		C D	D3-1	48	12			4.00																		INSTALL NEW D3-1 SIGN OVER THE R1-2 SIGN LOCATED 120' NORTH OF POLE # 19 / 40. INSTALL SINGLE FACED SIGNS ON BOTH SIDES OF POST, RIVOT IN PLACE.		14	
		D	R1-2	36	36			3.89								1.00		13.5 ~~15~~								INSTALL NEW R1-2 SIGN AND POST. LOCATE 120' NORTH OF POLE # 19 / 40	X		
NB	MM 0.054, RT.	A B	D3-1	30	8								X		X											REMOVE EXISTING D3-1 SIGN AND POST. LOCATE 130' NORTH OF POLE # 19 / 40			
NB	MM 0.056, RT.	C	R1-2	36	36			3.89								1.00		14.0 ~~15~~								INSTALL NEW R1-2 SIGN AND POST. LOCATE 140' NORTH OF POLE # 19 / 40	X		
NB	MM 0.056, RT.	B	W12-1	30	30			6.25								1.00		14.0 ~~15~~								INSTALL NEW W12-1 SIGN AND POST. LOCATE 145' NORTH OF POLE # 19 / 40	X		
NB	MM 0.075, RT.	D	R1-2	36	36			3.89								1.00		14.0 ~~15~~								INSTALL NEW R1-2 SIGN AND POST. LOCATE 70' SOUTH OF POLE # NET / 34 / 1	X		
NB	MM 0.100, RT.	A	R2-1	24	30			5.00								1.00		14.0 ~~15~~								INSTALL NEW R2-1 SIGN AND POST. LOCATE 65' NORTH OF POLE # NET / 34 / 1	X		
								SF 48.92	SF	EA 1 5				EA 1		EA 7	FT ~~105~~ 112.5			EA	LB							

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

										EA	EA	EA	EA 1	EA	EA 1		FT	FT 105	FT		LB	LB	LB	LB				

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
ENOSBURG TRAFFIC SIGN SUMMARY SHEET 1
SHEET 27 **OF** 107