STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

ENOSBURG
PERLEY RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 2.320, RT.	A	W5-1	36	36		ROAD NARROWS	9.00								2.00		14.0 14.0 ~~30~~								INSTALL NEW W5-1 SIGN AND POST. LOCATE IT 250' SOUTH AND ACROSS FROM TH # 16	X		
SB	MM 2.475, LT.	EF		6	8		(2) TYPE II - 6" x 8" WHITE DELINEATORS											↓								INSTALL NEW WHITE DELINEATOR (2) BACK-TO-BACK ON ONE POST ADJACENT TO TREE THAT IS CLOSE TO SHOULDER. LOCATE IT 575' NORTH OF TH # 16		5	
SB	MM 2.498, LT.	EF		6	8		(2) TYPE II - 6" x 8" WHITE DELINEATORS											↓								INSTALL NEW WHITE DELINEATOR (2) BACK-TO-BACK ON ONE POST ADJACENT TO TREE THAT IS CLOSE TO SHOULDER. LOCATE IT 697' NORTH OF TH # 16		5	
SB	MM 2.572, LT.	EF		6	8		(2) TYPE II - 6" x 8" WHITE DELINEATORS											↓								INSTALL NEW WHITE DELINEATOR (2) BACK-TO-BACK ON ONE POST ADJACENT TO TREE THAT IS CLOSE TO SHOULDER. LOCATE IT 830' SOUTH AND ACROSS FROM POLE # 72 / 15		5	
SB	MM 2.670, LT.	EF		6	8		(2) TYPE II - 6" x 8" WHITE DELINEATORS											28								INSTALL NEW WHITE DELINEATOR (2) BACK-TO-BACK ON ONE POST ADJACENT TO TREE THAT IS CLOSE TO SHOULDER. LOCATE IT 312' SOUTH AND ACROSS FROM POLE # 72 / 15		5	
NB	MM 2.716, RT.	A	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25								1.00		14.0 ~~15~~								INSTALL NEW VW-054 SIGN AND POST. LOCATE IT 70' SOUTH OF POLE # 72 / 15		14	
SB	MM 2.729, LT.	F	W5-1	36	36		ROAD NARROWS	9.00								2.00		30								INSTALL NEW W5-1 SIGN AND POST. LOCATE IT ACROSS FROM POLE # 72 /15	X		
SB	MM 2.761, LT.	F	W8-3	36	36		PAVEMENT ENDS	9.00								2.00		14.0 16.0 30								INSTALL NEW W8-3 SIGN AND POST. LOCATE IT ACROSS FROM POLE # 725 / 2	X		
NB	MM 2.799, RT.	A	TOWN SIGN	30	30		HIDDEN DRIVE AHEAD						X		X											REMOVE EXISTING SIGN AND POST LOCATED 15' NORTH OF POLE # 725 / 3 / 19			
NB	MM 2.833, RT.	A	VW-054	30	30		HIDDEN DRIVE RIGHT	6.25								1.00		16.0 ~~15~~								INSTALL NEW VW-054 SIGN AND POST. LOCATE IT 100' SOUTH OF POLE # 18 / 1/2		14	
										EA	EA	EA	EA 1	EA	EA 1		FT	FT ~~105~~	FT		LB	LB	LB	LB					
								SF 39.50	SF	EA 1				EA 1		EA 8	FT ~~120~~ 146			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn **PLOT DATE:** 16-JUL-2012
PROJECT LEADER: JLS **DRAWN BY:** TDS
DESIGNED BY: NLA **CHECKED BY:** NLA
ENOSBURG TRAFFIC SIGN SUMMARY SHEET 3 **SHEET** 29 **OF** 107