STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

ENOSBURG
PERLEY RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 3.065, RT.	A	W2-2L	30	30			6.25								1.00		16.0 ~~15~~								INSTALL NEW W2-2 SIGN AND POST. LOCATE IT ADJACENT TO POLE # 092 / 15	X		
		A	W16-8P	24	8		River St	1.34																		INSTALL NEW W16-8P SIGN BELOW THE W2-2 SIGN LOCATED ADJACENT TO POLE # 092 / 15. RIVOT SINGLE FACED STREETNAME SIGNS TO BOTH SIDES OF POST.		14	
SB	MM 3.112, LT.	EF	D3-1	36	12		River St	3.00					2 ~~X~~		X	1.00		15								REPLACE EXISTING D3-1 SIGN AND POST. LOCATE 15' CLOSER TO INTERSECTION. RIVOT SINGLE FACED STREETNAME SIGNS ON BOTH SIDES OF POST.		14	
SB	MM 3.112, LT.	EF	D3-1	36	12		River St	3.00																		RIVOT SINGLE FACED STREETNAME SIGNS ON BOTH SIDES OF POST.		14	
SB	MM 3.497, LT. TO MM 3.537, LT.	EF		6	8		(6) TYPE II - 6" x 8" WHITE DELINEATORS											27.0								INSTALL NEW DELINEATOER (6) BACK-TO-BACK 70' APART ON 3 POSTS, INSTALL FIRST POST 106' SOUTH AND ACROSS FROM POLE # 7		5	
SB	MM 3.595, LT.	G	VD-024	60	10		Enosburg | Berkshire						X		X											REMOVE EXISTING VD-024 SIGN AND POST LOCATED 70' NORTH AND ACROSS FROM POLE # 6			
SB	MM 3.595, LT.	F	R2-1	24	30		SPEED LIMIT 50	5.00					1			1.00		14.0 ~~15~~								INSTALL NEW R2-1 SIGN AND POST. LOCATE IT 70' NORTH AND ACROSS FROM POLE # 6	X		
NB	MM 3.595, RT.	C	VD-024	72	10		Berkshire | Enosburg	5.00								2.00		11.0 ~~30~~ 11.0								INSTALL NEW VD-024 SIGN AND POST. LOCATE IT 70' NORTH OF POLE # 6		14	
							NICHOLS RD																						
WB	MM 0.028, LT.	F													X											REMOVE EXISTING EMPTY POST LOCATED 150' +/- EAST OF INTERSECTION			
WB	MM 0.066, LT.	F	W3-2	30	30			6.25					1			1.00		14.0 ~~15~~								INSTALL NEW W3-2 SIGN AND POST. LOCATE IT 300' +/- EAST OF ISLAND	X		
										EA	EA	EA	EA ~~2~~	EA	EA 3		FT	FT 90	FT		LB	LB	LB	LB					
								SF 29.84	SF	EA ~~2~~ 5				EA 3		EA 6	FT ~~90~~ 108			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA