

# TRAFFIC SIGN SUMMARY SHEET 1

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS		SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS			EXISTING POST		SQUARE STEEL (in)			TUBULAR STEEL (in)				SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL								
				WIDTH	HEIGHT			"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	P-1-A-N	P-1-M-O-V-E	P-1-O-S-T-S	1.75	2.00	2.50	FOUNDATION	3.00			3.50	4.00	5.00	DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER			
																	lb/ft	lb/ft	lb/ft		lb/ft			lb/ft	lb/ft							
WB	MM 0.011, LT.	F	R1-1	30	30			6.25				X	X	1.00			14.0	15						REPLACE EXISTING R1-1 SIGN AND POST LOCATED 60' EAST OF VT-15 INTERSECTION	X							
EB	MM 0.015, RT.	A	R2-1	24	30			5.00																INSTALL NEW R2-1 BELOW EXISTING VR-017 SIGN LOCATED 80' EAST OF VT-15 INTERSECTION	X							
		A	VR-017	24	30			5.00				X	X	1.00			15							REPLACE EXISTING VR-017 SIGN AND POST LOCATED 80' EAST OF VT-15 INTERSECTION	X							
EB	MM 0.197, RT. TO MM 0.282, RT.	AB		6	8		(10) TYPE II - 6" x 8" WHITE DELINEATORS										40.0							INSTALL NEW DELINEATORS (10) BACK-TO-BACK 85' APART ON 5 POSTS. INSTALL FIRST POST ACROSS FROM POLE # 5 / NET / 3			5					
WB	MM 0.280, LT.	H	R1-1	30	30			6.25				X	X	1.00			15							REPLACE EXISTING R1-1 SIGN AND POST LOCATED ACROSS FROM POLE # 7 / 73 / 5	X							
WB	MM 0.284, LT.	EF	D3-1	60	12			5.00				X	X	2.00			14.0	30	14.0					REPLACE EXISTING D3-1 SIGN INSTALL ON 2 POSTS LOCATED ACROSS FROM POLE # 7 / 73 / 5			13					
EB	MM 0.568, RT.	A	W1-5R	30	30			6.25						1.00			16.0	15						INSTALL NEW W1-5 SIGN AND POST. LOCATE IT 25' WEST OF POLE # 15	X							
		A	W7-3A	24	18			3.00																INSTALL NEW W7-3A SIGN BELOW THE W1-5 SIGN LOCATED 25' WEST OF POLE # 15	X							
WB	MM 0.600, LT.	E	W1-6R	48	24			8.00						2.00			13.0	30	13.0					INSTALL NEW W1-6 SIGN AND POSTS. LOCATE IT 28' WEST OF POLE # 14	X							
WB	MM 0.600, LT.	F	W1-6L	48	24			8.00						2.00			13.0	30	13.0					INSTALL NEW W1-6 SIGN AND POSTS. LOCATE IT 20' WEST OF POLE # 14	X							
EB	MM 0.701, RT.	A	S3-1	36	36	FYG		9.00				X	X	2.00			15.0	15.0	30					INSTALL NEW S3-1 SIGN AND POSTS. LOCATE IT 510" EAST AND ACROSS FROM POLE # 14	X							
<p>FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".</p>																																