STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

SHELDON - HIGHGATE - FRANKLIN
RICE HILL RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft	SQUARE STEEL (in) 2.00 lb/ft	SQUARE STEEL (in) 2.50 lb/ft	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft	TUBULAR STEEL O/(in) 3.50 lb/ft	TUBULAR STEEL O/(in) 4.00 lb/ft	TUBULAR STEEL O/(in) 5.00 lb/ft	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
																	1.88	2.42	3.35		7.60	9.00	10.80	14.60					
		H	R1-1	30	30		STOP	6.25					X		X	1.00		14.0 ~~15~~								REPLACE THE EXISTING R1-1 SIGN AND POST, LOCATE IT ACROSS FROM POLE # VTELEC/99C/14	X		
SB	MM 0.535, LT. + 400 FT.		W3-1	30	30			6.25								1.00		14.0 ~~15~~								INSTALL A NEW W3-1 SIGN LOCATE IT 400' ACROSS AND WEST OF POLE # VTELEC/99C/14	X		
SB	MM 0.549, LT.	EF	D3-1	24	6		Dunton Rd						~~X~~		X											REMOVE THE D3-1 SIGN AND POST LOCATED ADJACENT TO POLE # VTELEC /99C/14			
SB	MM 0.594, LT.	F	W2-2R	30	30			6.25								1.00		16.0 ~~15~~								INSTALL A NEW W2-2 SIGN AND POST. LOCATE IT 25' SOUTH OF POLE # VTELEC/99C/16	X		
		F	W16-8P	24	8		Dunton Rd	1.34																		INSTALL A NEW W16-8P SIGN BELOW THE W2-2 SIGN LOCATED 25' SOUTH OF POLE # VTELEC/99C/16		14	
SB	MM 0.711, LT.	F	TOWN SIGN	12	18		WATCH FOR CHILDREN						~~X~~		X											REMOVE SIGN AND POST LOCATED 80' SOUTH OF POLE # VTELEC / 99C / 20			
NB	MM 1.064, RT.	A	W1-2L	30	30			6.25								1.00		15								INSTALL A NEW W1-2 SIGN AND POST. LOCATE IT 750' SOUTH OF POLE # 35	X		
SB	MM 1.146, LT.	F	W1-2R	30	30			6.25								1.00		15								INSTALL A NEW W1-2 SIGN AND POST. LOCATE IT 320' SOUTH AND ACROSS FROM POLE # 35	X		
NB	MM 1.200, RT.	A	W1-2R	30	30			6.25								1.00		15								INSTALL A NEW W1-2 SIGN AND POST. LOCATE IT 25' SOUTH OF POLE # 35	X		
SB	MM 1.229, LT. TO MM 1.255, LT.	E F		6	8		(6) TYPE II - 6" x 8" WHITE DELINEATORS									3.0		24.0								INSTALL NEW DELINEATORS (6) BACK - TO - BACK 60' APART ON 3 POSTS. INSTALL FIRST POST 120' NORTH AND ACROSS FROM POLE # 35		5	
										EA	EA	EA	EA ~~3~~ 1	EA	EA 3		FT	FT ~~90~~ 113	FT		LB	LB	LB	LB					
							6.0 DELINEATORS	SF 38.84	SF	EA ~~3~~ 1				EA 3		EA 6	FT ~~90~~ 113			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn **PLOT DATE:** 16-JUL-2012
PROJECT LEADER: JLS **DRAWN BY:** TDS
DESIGNED BY: NLA **CHECKED BY:** NLA
SHELDON-HIGHGATE-FRANKLIN TSS SHEET 2 **SHEET** 39 **OF** 107