STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

SHELDON - HIGHGATE - FRANKLIN
RICE HILL RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 1.464, RT.	A	W1-3L	30	30			6.25								1.00		17.0 ~~15~~								INSTALL A NEW W1-3 L SIGN AND POST. LOCATE IT 465' SOUTH OF POLE # VTELEC/99C/44	X		
		A	W13-1	18	18			2.25																		INSTALL A NEW W13-1 SIGN BELOW THE W1-3 L SIGN. LOCATE IT 465' SOUTH OF POLE # VTELEC/99C/44	X		
NB	MM 1.513, RT.	A B	W1-8L W1-8R	18 18	24 24			3.00 3.00								1.00		12.0 ~~15~~								INSTALL THE TWO CHEVRONS ON AN ADJUSTABLE BRACKET. LOCATE ASSEMBLY 206' SOUTH OF POLE # VTELEC/99C/44	X		
NB	MM 1.536, RT.	A B	W1-8L W1-8R	18 18	24 24			3.00 3.00								1.00		12.0 ~~15~~								INSTALL THE TWO CHEVRONS ON AN ADJUSTABLE BRACKET. LOCATE ASSEMBLY 85' SOUTH OF POLE # VTELEC/99C/44	X		
NB	MM 1.559, RT.	A B	W1-8L W1-8R	18 18	24 24			3.00 3.00								1.00		12.0 ~~15~~								INSTALL THE TWO CHEVRONS ON AN ADJUSTABLE BRACKET. LOCATE ASSEMBLY 40' NORTH OF POLE # VTELEC/99C/44	X		
SB	MM 1.616, LT.	E F	W1-8R W1-8L	18 18	24 24			3.00 3.00								1.00		15								INSTALL THE TWO CHEVRONS ON AN ADJUSTABLE BRACKET. LOCATE ASSEMBLY 170' SOUTH AND ACROSS FROM POLE # 142	X		
SB	MM 1.637, LT.	E F	W1-8R W1-8L	18 18	24 24			3.00 3.00								1.00		14.0 ~~15~~								INSTALL THE TWO CHEVRONS ON AN ADJUSTABLE BRACKET. LOCATE ASSEMBLY 60' SOUTH AND ACROSS FROM POLE # 142	X		
SB	MM 1.658, LT.	E F	W1-8R W1-8L	18 18	24 24			3.00 3.00								1.00		15								INSTALL THE TWO CHEVRONS ON AN ADJUSTABLE BRACKET. LOCATE ASSEMBLY 53' NORTH AND ACROSS FROM POLE # 142	X		
								SF 44.50	SF	EA	EA	EA	EA	EA	EA	EA 7	FT	FT ~~105~~	FT ~~105~~ 97.0	EA	LB	LB	LB	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
SHELDON-HIGHGATE-FRANKLIN TSS SHEET 3

PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA
SHEET 40 OF 107