STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

STARKSBORO
BIG HOLLOW RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK	SIGN DETAIL DETAIL IN SHSM	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STANDARD SHEET NUMBER
NB	MM 0.190, RT. TO MM 0.271, RT.	A B		6	8		(16) TYPE II - WHITE DELINEATORS											72.0								INSTALL NEW DELINEATORS (16) BACK-TO-BACK 55' APART ON 8 POSTS, INSTALL FRIST POST 42' NORTH OF NEW TURN LEFT ASSEMBLY		5	
SB	MM 0.297, LT.	F	W1-1R	30	30			6.25								1.00		15								INSTALL NEW W1-1 R SIGN AND POST. LOCATE IT 75' SOUTH OF POLE # GMP / 9	X		
NB	MM 0.817, RT.	A B		6	8		(2) TYPE II - 6" x 8" WHITE DELINEATORS											18.0								INSTALL NEW DELINEATORS (2) BACK-TO-BACK ON 1 POST 875' SOUTH OF POLE # VERM TEL CO / 14, ADJACENT TO TREE NEAR ROADWAY		5	
NB	MM 0.817, RT.	A B		6	8		(2) TYPE II - 6" x 8" WHITE DELINEATORS											18.0								INSTALL NEW DELINEATORS (2) BACK-TO-BACK ON 1 POST 274' SOUTH OF POLE # VERM TEL CO / 14		5	
SB	MM 0.977, LT.	F	R2-1	24	30			5.00					X		X	1.00		11.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 32' SOUTH AND ACROSS FROM POLE # VERM TEL CO / 14	X		
NB	MM 1.000, RT.	D	R1-2	36	36			3.89					X		X	1.00		13.0 ~~15~~								REPLACE EXISTING R1-2 SIGN AND POSTS LOCATED 90' NORTH OF POLE # VER TEL CO / 14	X		
NB	MM 1.001, RT.	A	R2-1	24	30			5.00					X		X	1.00		13.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 160' NORTH OF POLE # VER TEL CO / 14	X		
NB	MM 1.545, RT.	A	TOWN SIGN	12	18								X		X											REMOVE EXISTING SIGN AND POST LOCATED 45' SOUTH AND ACROSS FROM POLE # GMP / 26			
SB	MM 1.920, LT.	F	TOWN SIGN	12	18								X		X											REMOVE EXISTING SIGN AND POST LOCATED 10' NORTH OF MAIL BOX # 1901			
SB	MM 2.159, LT.	F	R2-1	24	30			5.00					X		X	1.00		13.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 365' SOUTH AND ACROSS FROM POLE # 33 / 86D / 36 / X	X		
SB	MM 2.212, LT.	H	R1-2	36	36			3.89								1.00		13.0 ~~15~~								INSTALL NEW R1-2 SIGN AND POSTS 85' SOUTH AND ACROSS FROM POLE # 33 / 86D / 36 / X	X		
SB	MM 2.223, LT.	K	R1-2	36	36							1	X		X											REMOVE EXISTING R1-2 SIGN AND POST LOCATED 30' SOUTH AND ACROSS FROM POLE # 33 / 86D / 36 / X	X		
										EA	EA	EA	EA 7	EA	EA 7		FT	FT ~~90~~	FT		LB	LB	LB	LB					
								SF 29.03	SF	EA 7				EA 7		EA 6	FT ~~90~~ 186			EA	LB								

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA