STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

STARKSBORO
BIG HOLLOW RD

DIRECTION	MILEMARKER, STATION, OR SIGN NUMBER	LOCATION	MANUAL ON UNIFORM TRAFFIC DEVICES OR STATE CODE	SIGN DIMENSIONS WIDTH	SIGN DIMENSIONS HEIGHT	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXISTING POST RETAIN	EXISTING POST REMOVE	NO. OF NEW POSTS	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.00 lb/ft 2.42	SQUARE STEEL (in) 2.50 lb/ft 3.35	TUBULAR STEEL O/(in) FOUNDATION	TUBULAR STEEL O/(in) 3.00 lb/ft 7.60	TUBULAR STEEL O/(in) 3.50 lb/ft 9.00	TUBULAR STEEL O/(in) 4.00 lb/ft 10.80	TUBULAR STEEL O/(in) 5.00 lb/ft 14.60	SIGN FRAME REQUIRED	REMARKS (SHSM = STANDARD HIGHWAY SIGN & MARKING BOOK)	SIGN DETAIL: DETAIL IN SHSM	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: STANDARD SHEET NUMBER
NB	MM 2.248, RT.	A	R2-1	24	30		SPEED LIMIT 30	5.00								1.00		13.0 ~~15~~								INSTALL NEW R2-1 SIGN AND POST. LOCATE IT 105' NORTH OF POLE # 33 / 86D / 36 / X	X		
NB	MM 2.292, RT.	A	R2-1	24	30		SPEED LIMIT 30						X		X											REMOVE EXISTING R2-1 SIGN AND POST LOCATED 340' NORTH OF POLE # 33 / 86D / 36 / X			
SB	MM 2.521, LT.	F E	TOWN SIGN	12	18		SLOW CHILDREN						X		X											REMOVE EXISTING SIGN AND POST LOCATED 10' SOUTH OF MAIL BOX # 2513			
NB	MM 3.946, RT. TO MM 3.988, RT.	A B		6	8		(8) TYPE II - 6" x 8" WHITE DELINEATORS 2 MORE INSTALLED ON 7/8											18.0 36.0								INSTALL NEW DELINEATORS (8) BACK-TO-BACK 55 " APART ON 4 POSTS, INSTALL FIRST POST 570' SOUTH OF POLE # V / E / CO-OP / 33 / 86D		5	
SB	MM 4.170, LT.	F	R2-1	24	30		SPEED LIMIT 30	5.00					X		X	1.00		13.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 612' NORTH AND ACROSS FROM POLE # V / E / CO-OP / 33 / 86D	X		
NB	MM 4.218, RT.	A B	D3-1	66	12		Shaker Hill Rd	5.50					I			1.00		14.0 ~~15~~								INSTALL NEW D3-1 SIGN AND POST. LOCATE IT 866' NORTH OF POLE # V / E / CO-OP / 33 / 86D		15	
NB	MM 4.218, RT.	D	R1-2	36	36		YIELD	3.89			I		X		X	1.00		~~15~~								REPLACE EXISTING R1-2 SIGN AND POSTS LOCATED 875' NORTH OF POLE # V / E / CO-OP / 33 / 86D	X		
NB	MM 4.241, RT.	A	R2-1	24	30		SPEED LIMIT 30	5.00					I			1.00		14.0 ~~15~~								INSTALL NEW R2-1 SIGN AND POST LOCATED 990' NORTH OF POLE # V / E / CO-OP / 33 / 86D	X		
SB	MM 4.552, LT.	F	R2-1	24	30		SPEED LIMIT 30	5.00					X		X	1.00		14.0 ~~15~~								REPLACE EXISTING R2-1 SIGN AND POST LOCATED 925' SOUTH AND ACROSS FROM POLE # CTC VT / 44	X		
SB	MM 4.570, LT.	H	R1-2	36	36		YIELD	3.89								1.00		14.0 ~~15~~								INSTALL NEW R1-2 SIGN AND POSTS 830' SOUTH AND ACROSS FROM POLE # CTC VT / 44	X		
SB	MM 4.582, LT.	H	R1-2	36	36		YIELD						X		X											REMOVE EXISTING R1-2 SIGN AND POST LOCATED 815' SOUTH AND ACROSS FROM POLE # CTC VT / 44			
										EA	EA I	EA	EA ~~6~~	EA	EA 6		FT	FT ~~105~~	FT				LB	LB	LB	LB					
							10 DELINEATORS	SF 33.28	SF	EA I	EA ~~6~~	EA 7		EA 6		EA 7	FT	FT ~~105~~ 118		EA	LB										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDE".

PROJECT NAME: STATEWIDE NORTHWEST REGION
PROJECT NUMBER: STP HRRR(13)

FILE NAME: 12k020wrk.dgn
PROJECT LEADER: JLS
DESIGNED BY: NLA
PLOT DATE: 16-JUL-2012
DRAWN BY: TDS
CHECKED BY: NLA

STARKSBORO TRAFFIC SIGN SUMMARY SHT 3 **SHEET** 47 **OF** 107